



August 9, 2024

Mr. Tyler Quattrocchi, PE
Engineering Project Manager
Village of Schaumburg
714 S. Plum Grove Rd.
Schaumburg, IL 60193

Subject: Bode Road Force Main Final Design

Dear Mr. Quattrocchi,

Please find under this transmittal one electronic copy of our Proposal for the Bode Force Main Final Design Project.

Why Ciorba?

Engineering Experience. Ciorba Group has been involved in the assessment, design, and / or construction management of 35 lift station and force main projects within the past 7 years alone. All of the staff presented in this proposal have a passion for the multi-disciplinary tasks needed for excellent lift station and force main design. Key players on our team also have experience as Resident Engineers and Inspectors for lift station and force main projects which translate to thoughtful designs that work during construction.

Local Knowledge. Ciorba Group's involvement with the Bode Lift Station began in the Summer of 2017 as the Phase III Construction Engineer for the *Pumping Station Improvement Program*, designed by another firm. During our inspection, Ciorba pinpointed a pump capacity issue and has been assisting the Village to design, permit, and construct a retrofit to correct the problem. Ciorba partnered with the Village to increase the original 2017 start-up pump capacity of 750 gpm to the current 2024 start-up pump capacity of 1,250 gpm to effectively serve the upstream basin during dry and wet weather.

Proven Success. We encourage you to ask our other municipal clients how we have done.

Client	Ciorba Lift Station Projects	Contact
Village of Buffalo Grove	5 Sites	Kyle Johnson, P.E. Assistant Public Works Director 847.259.2523 KJohnson@vbg.org
	- 4 as Condition Assessment Engineer	
	- 5 as Design Engineer	
	- 4 as Construction Engineer	
Village of Mount Prospect	4 Sites	Casey Botterman Water / Sewer Superintendent 847.870.5640 CBotterman@mountprospect.org
	- 4 as Design Engineer	
	- 4 as Construction Engineer	
	- 1 as Public Messaging Support	
Village of Schaumburg	5 Sites	Brian Wagner Utility Superintendent 847.923.6641 bwagner@schaumburg.com
	- 2 as Condition Assessment Engineer	
	- 2 as Design Engineer	
	- 3 as Construction Engineer	

Should you have any questions about this proposal, please contact me at 773.892.9795 or at lmattson@ciorba.com at any time.

Sincerely,

Ciorba Group, Inc.

Luke A. Mattson, PE
Water Resources Project Manager



PROJECT UNDERSTANDING

Ciorba Group History with Bode Lift Station and Force Main

Ciorba Group’s involvement with the Bode Lift Station began in the Summer of 2017 as the Phase III Construction Engineer for the *Pumping Station Improvement Program*, which included the reconstruction of both the Bode Road and Toys Lift Stations. Ciorba Group enforced the design that was prepared by another Engineering Firm and provided re-design as needed throughout the construction process.

During the startup of the Bode Lift Station, Ciorba Group identified a discrepancy in the pump capacity of the new station compared to the existing station and notified the Village of Schaumburg. We pinpointed the issue as a pump sizing error in the design and spent the next 5-years assisting the Village in coordinating with MWRDGC on a fix to the situation.





2017 Insertion Value Installed on Existing 14” Force Main

Ciorba Group permitted the retrofit design in 2019 and then again in 2022, and also assisted the Village in closing out the original permit from 2015. We are now in the closing stages of the retrofit construction, addressing punch list items. Throughout this process, Ciorba partnered with the Village to increase the original 2017 start-up pump capacity of 750 gpm to the current 2024 start-up pump capacity of 1,250 gpm to effectively serve the upstream basin during dry and wet weather.

Design Considerations

The Village of Schaumburg delayed the demolition of the original lift station after finding the existing 14” force main to be in poor condition during the inspection as part of a pigging project. Redundancy during construction is of utmost importance. Any disruption to the lift station operation impacts the upstream population of 5,115 people in the 491-acre basin. In addition to the station redundancy, it is necessary to minimize the downtime of the lift stations to two hours. This requires the full reconstruction and testing of the new force main while the station continues to operate. The following exhibits offer a preliminary alignment consideration in order to accomplish this. Snapshots along Bode Road and Braintree Drive are offered.



----- Ex. Force Main	----- Ex. Water Main	----- Ex. Elec. (Underground)
----- Ex. San. Sewer	----- Ex. Drainage Ditch	-A- Ex. Elec. (Aerial)

The force main along Bode Road will likely be constructed within the right of way, north and parallel to the existing force main unless there is easement available to the south. The force main along Braintree will likely be located under pavement based the parkways being occupied with existing Village water main, sanitary sewer, and the existing 14” force main that must remain active during construction. Franchise utilities such as gas, electric, and communications are also likely to be located within the parkways.

PROJECT UNDERSTANDING

Ciorba's design will consider both open cut and trenchless construction technologies for the Village's consideration.

Once the force main has been constructed and pressure tested, the connection of the new force main shall be made to the existing 8" force main exiting from the north side of the new lift station. We recommend extending the 14" force main up to the turning point to reduce the length of 8" pipe along the final route. This will result in an increase in the flow rate of the new pumps by reducing friction head loss. The following exhibit illustrates the proposed connection sequence to minimize the down time of the lift stations to less than an hour.


Permitting

Ciorba Group recently helped the Village close the original MWRDGC permit for the 2017 reconstruction of the lift station (Permit 15-057) by assuming the responsibility of the original design consultant who was no longer able to sign. Ciorba is currently in the process of closing the permit for the retrofit improvement (Permit 2022-0270). This project will require a third MWRD permit for the new force main construction. Ciorba will be able to provide consistency throughout this complex permitting process.

Scope of Work

Ciorba Group agrees with the scope of work identified in the RFP and clarified via Addendum and the following assumptions:


- Hardscape restoration (pavements, curb, sidewalk, driveways) will only be at those locations impacted by the force main work.
- Based on our preliminary assessment of force main alignment, we propose to design the force main without impacting existing ADA ramp locations.
- Specifications will be based on the current editions of the IDOT Standard Specifications and the Standard Specification for Water And Sewer Construction, with specific Special Provisions written to amend these specifications as required. Specifications will not follow the Master Format.



2017 Insertion Valve Installed on Existing 14" Force Main



Old Bypass Structure at Bode Lift Station



Bode Road Lift Station Construction Inspection

Ciorba Group’s involvement with the Bode Lift Station began in the Summer of 2017 as the Phase III Construction Engineer for the Pumping Station Improvement Program, which included the reconstruction of both the Bode Road and Toys Lift Stations. Ciorba Group enforced the design that was prepared by another Engineering Firm and provided re-design as needed throughout the construction process.

The scope of construction work for the lift station included the conversion of the wet/dry system to a duplex submersible station. This work also included new process piping, metering, a backup generator, ground level controls, and a prefabricated enclosure building. The work also included the construction of 8” and 16” ductile iron force main.

During construction, Ciorba Group recommended design changes to

coordinate multiple control suppliers and integrators to streamline the control equipment in the generator room. Ciorba also recommended process piping changes to offer better operational options for Village public works staff.

During the startup of the Bode Lift Station, Ciorba Group identified a discrepancy in the pump capacity of the new station compared to the existing station and notified the Village of Schaumburg. We pinpointed the issue as a pump sizing error in the design by another consultant and spent the next 5-years assisting the Village in coordinating with MWRDGC on a fix to the situation.

Ciorba Group offered value to the Village of Schaumburg by working to identify cost impacts of the capacity discrepancy for reimbursement.



CLIENT Village of Schaumburg	PROJECT TEAM Project Manager/ Resident Engineer Luke Mattson, PE
CONTACT Mr. Brent McQueen, PE, CFM, CPESC Engineering Division Manager 847.923.6628	SCOPE OF SERVICE ► Construction Observation
CONSTRUCTION COST \$900,000	

Lift station type: Sanitary Sewer Duplex Submersible Lift Station	Lift station capacity: 750 GPM @ 55’ TDH 2 x 20 HP Pumps
---	---

Bode Lift Station Retrofit

Ciorba Group provided preliminary engineering, final design, and is currently providing construction inspection for the Bode Lift Station Retrofit. This project is the continuation of the Bode Lift Station Construction Project where Ciorba Group served as the Construction Engineer.

Ciorba Group permitted the retrofit design in 2019 and then again in 2022, and also assisted the Village in closing out the original permit from 2015. We are now in the closing stages of the retrofit construction, addressing punch list items. Throughout this process, Ciorba partnered with the Village to increase the original 2017 start-up pump capacity of 750 gpm to the current 2024 start-up pump capacity of 1,250 gpm to effectively serve the upstream basin during dry and wet weather.

This project consists of the retrofit upgrades of the existing lift station by replacing the original undersized 20 hp pumps with new 34 hp pumps. Due to the increase in horsepower, the retrofit also required the installation of soft starters to limit the in-rush current during pump startup. This electrical and control panel work required modification to the existing pump control panel, SCADA panel, and the mounting of a new starter panel. Demolition work under this project were recently eliminated and have been added to the scope of the Bode Road Force Main Final Design project.

Ciorba Group continues to offer value to the Village of Schaumburg by providing consistent technical and project management support for a facility that began upgrades 7-years ago in 2017.



CLIENT Village of Schaumburg	PROJECT TEAM Project Manager/Project Engineer/ Resident Engineer Luke Mattson, PE Water Resource Engineer Corinne Gibbs, PE Electrical Engineer Katrina Lopez, PE QA/QC Engineer Tony Wolff, PE, CFM
CONSTRUCTION COST: \$545,000	
CONTACT Mr. Brent McQueen, PE, CFM, CPESC Engineering Division Manager 847.923.6628	SCOPE OF SERVICE ► Preliminary Engineering ► Final Design ► Construction Observation

Lift station type: Sanitary Sewer Duplex Submersible Lift Station	Lift station capacity: 1,250 GPM @ 65’ TDH 2x34 HP Pumps
---	---

Project Request #2024-RFP-064
Title: Bode Rd Force main Final Design

6. Pricing Sheet(s)

NOTICE TO VENDORS: Failure to complete the following Pricing Sheet(s) may be cause for rejection of your submittal. If you are not bidding on an entire group, please provide \$0.00 as the cost for such items.

NOTE: Unit prices shall include the cost of delivery (if applicable).

Line Item	Description	Quantity	Unit of Measure	Unit Cost	Total
1	Phase II Design of the Bode Rd Force Main Replacement	1	ls	\$ 61,908.97	\$ 61,908.97
TOTAL \$ 61,908.97					



Fee Summary

Ciorba Group proposes the following fees to complete **Design Phase** of the Bode Road Force Main Project, including approximately 2,600 feet of 14” force main.

Design Engineering

Ciorba Labor & Overhead Costs:	\$ 54,511.22
Ciorba In-House Direct Costs:	\$ 422.75
Soil Borings / CCDD Sampling (SMC):	\$ 6,975.00
Total Design Engineering Fee:	\$ 61,908.97

The design fee includes soil borings and soil sampling at 500-foot intervals for the preparation of an LPC-662 package to be provided to the contractors bidding the project for CCDD purposes.

The tables on the following pages provide detailed staff hour and direct cost estimates broken out by task.



Cost Estimate of
Consultant Services
(Direct Labor Multiple)

Firm Ciorba Group, Inc

Date 08/07/24

DBE	ITEM	MANHOURS	PAYROLL	(3+R) TIMES PAYROLL	DIRECT COSTS	SERVICES BY OTHERS	TOTAL	% OF GRAND TOTAL
		(A)	(B)	(C)	(D)	(E)	(C+D+E)	
	Meetings, Data Collection & Coordination	10	\$ 631.25	\$ 1,893.75	\$ 32.75		\$ 1,926.50	3%
	Survey	56	\$ 2,424.00	\$ 7,272.00	\$ 390.00		\$ 7,662.00	12%
	Water Resources	168	\$ 8,594.09	\$ 25,782.27	\$ -		\$ 25,782.27	42%
	Engineering Studies/Plans	40	\$ 2,064.95	\$ 6,194.84	\$ -		\$ 6,194.84	10%
	Quantity, Specifications & Estimates	48	\$ 2,671.45	\$ 8,014.35	\$ -		\$ 8,014.35	13%
	Construction Engineering / Administration	4	\$ 265.63	\$ 796.89	\$ -		\$ 796.89	1%
	QC / QA	8	\$ 791.84	\$ 2,375.52	\$ -		\$ 2,375.52	4%
	Project Management & Administration	8	\$ 727.20	\$ 2,181.60	\$ -		\$ 2,181.60	4%
	Soil and Material Consultants					\$ 6,975.00	\$ 6,975.00	11%
	TOTALS	342	\$ 18,170.41	\$ 54,511.22	\$ 422.75	\$ 6,975.00	\$ 61,908.97	100%



Activity			Grand Total	Project Manager III	Project Manager II	Senior Engineer	Engineer II	Engineer I	Senior Technician
TOTAL			342	12	43	153	78	8	48
1.	Meetings, Data Collection & Coordination	Task Total:	10		4	6			
	0100 Meetings	Meetings	10		4	6			
	Meetings with Owner (Water Resources) (2 mtg x 2 hrs/mtg x 2 staff)		8		4	4			
	Meeting Minutes		2			2			
2.	Survey	Task Total:	56					8	48
	0210 Field Survey	Subtotal:	48					8	40
	Horizontal Topography		48					8	40
	0220 Process Survey	Subtotal:	8						8
	Base Sheet Development		8						8
3.	Water Resources	Task Total:	168		18	94	56		
	0340 Sanitary Sewer	Subtotal:	148		14	82	52		
	Conflict Investigation (Utilities)		12		2	6	4		
	Force Main Design		44		2	28	14		
	Force Main Plan and Profile Shets		40		2	22	16		
	Force Main Details		8		2	4	2		
	Hardscape Restoration Design		20		2	10	8		
	Erosion Control and Landscaping Plans		20		2	10	8		
	Force Main Design Report		4		2	2			
	0360 Permits	Subtotal:	20		4	12	4		
	Permit - IEPA (Water and Sanitary)		8		2	6			
	Permit- MWRDGC		12		2	6	4		
5.	Engineering Studies/Plans	Task Total:	40		5	21	14		
	0560 Contract Plans	Subtotal:	40		5	21	14		
	Title Sheet (x hrs/sheet)		2		1	1			
	Alignment, Ties and Benchmarks (x hrs/sheet)		2			2			
	Summary of Quantities (x hrs/sheet)		4			2	2		
	Plan Revisions		20		2	10	8		
	Disposition of Comments (hrs X submittal X total of # submittals)		12		2	6	4		
7.	Quantity, Specifications & Estimates	Task Total:	48		10	30	8		
	0700 Quantity, Specifications and Estimates	Subtotal:	48		10	30	8		
	Quantity Calculations and BOM (Water Resources)		20		4	8	8		
	Specifications (Water Resources)		18		2	16			
	Estimate of Time		2		2				
	Estimate of Cost		8		2	6			
8.	Construction Engineering / Administration	Task Total:	4		2	2			
	0840 Construction Assistance	Subtotal:	4		2	2			
	Assistance During Bidding		4		2	2			
9.	QC / QA	Task Total:	8	8					
	0900 QC / QA	Subtotal:	8	8					
	Water Resources QC/QA		8	8					
10.	Project Management & Administration	Task Total:	8	4	4				
	1000 Project Management & Administration	Subtotal:	8	4	4				
	Project Administration		4	4					
	Project Management		4		4				

DIRECT COSTS SUMMARY

Meetings, Data Collection & Coordination

Description	Unit	Unit Cost	Quantity	Extended Cost
Vehicle (mileage)	mile	\$ 0.655	50	\$ 32.75
				\$ 32.75 Total

Survey

Description	Unit	Unit Cost	Quantity	Extended Cost
Vehicle (day)	day	\$ 65.00	6	\$ 390.00
				\$ 390.00 Total