13379TITLE

10/18/24

13379

SHEET

OF 21

SITE IMPROVEMENT PLANS for

SCHAUMBURG ROHRMAN KIA

SCHAUMBURG, ILLINOIS **PROJECT NO:13379**

AMERICANS WITH DISABILITIES ACT (ADA), AND THE CODES AND BUILDING ORDINANCES OF THE CITY OF

REGISTERED PROFESSIONAL ENGINEER

LICENSED ARCHITECT / LANDSCAPE ARCHITECT /

PROFESSIONAL DESIGN FIRM NO.: 184-001157

DANIEL C. STEVENS, P.E. ILLINOIS REGISTRATION NO.: 062-057634

EXPIRATION DATE: 11/30/2025

 $^{\prime}$ To the best of our knowledge and belief, the drainage of surface waters will not be changed by the construction of this

changed, reasonable provisions have been made for collection and diversion of such surface waters into public areas, or drains

engineering practices so as to reduce the liklihood of damage to adjoining properties because of the construction of this development. The development shall not adversely increase flood elevations or decrease flood conveyance capacity

DRAINAGE CERTIFICATION

DANIEL STEVENS

upstream or downstream the project area.

ARCHITECT

LINDEN GROUP ARCHITECTS 10100 ORLAND PKWAY, #110 ORLAND PARK, IL 60467 708-799-4400

Contact the Metropolitan Water Reclamation District

of Greater Chicago <u>2 days</u>

■ WMOJobStart@mwrd.org

before starting work.

P (708) 588-4055

CALL J.U.L.I.E. 1-800-892-0123 WITH THE FOLLOWING:

S30, T42N, R8E 48 HOURS BEFORE YOU DIG.

EXCLUDING SAT., SUN. & HOLIDAYS

		INDEX
SHEET #	SHEET I.D.	SHEET DESCRIPTION
1	C1	COVER SHEET
2	GN	TYPICAL SECTIONS & GENERAL NOTES
3	ET	EXISTING CONDITIONS PLAN
4	DEMO	DEMOLITION PLAN
5	GM1	GEOMETRIC PLANS
6	GR1	GRADING PLANS
7	UT1	UTILITY PLANS
8-10	SE1-SE3	SOIL EROSION AND SEDIMENT CONTROL PLANS
11	S1	SPACECO SPECIFICATIONS
12	S2	CITY OF SCHAUMBURG SPECIFICATIONS
13-18	D1-D6	DETAILS
19	MWRD-GN	MWRD GENERAL NOTES
20	MWRD	MWRD WMO EXHIBIT
21	ADA	ADA RAMP DETAILS (TO BE PROVIDED AFTER INTIITAL REVIEW)

BENCHMARK


DESCRIPTION: SEE SHEET ET FOR


BENCHMARK INFORMATION

NOTE:

SPACECO, INC. IS TO BE NOTIFIED AT LEAST THREE (3) DAYS PRIOR TO STARTING CONSTRUCTION AND SHALL BE INCLUDED IN THE PRECONSTRUCTION MEETINGS

MWRD SEWER ROUTING MAP





. 🔿		
	11/21/24	
ENGINEER	DATE	ORDESSIONAL
DANIEL C. STEVENS, P.E.		
ILLINOIS REGISTRATION NO.: 062-057634 EXPIRATION DATE: 11/30/2025		DANIEL 31 C. STEVENS A STE
PROFESSIONAL DESIGN FIRM NO.: 184-001157 EXPIRATION DATE: 04/30/2025		* //LINOIS
THESE PLANS OR ANY PART THEREOF SHALL BE CONSIDERED VITHE SIGNATURE , SEAL, AND EXPIRATION DATE OF SEAL OF THE		

N:\Projects 13000-13999\13379\ENG\13379TITLE.dgn Default User=bmcgovern

GENERAL NOTES

- A. ALL PAVEMENT AND STORM SEWER CONSTRUCTION SHALL CONFORM TO THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION (SSRBC) ADOPTED JANUARY 1,2022, AND SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS ADOPTED JANUARY 1, 2024; BY ILLINOIS DEPARTMENT OF TRANSPORTATION AND ALL AMENDMENTS THERETO; AND IN ACCORDANCE WITH THE LATEST EDITION OF THE CODE OF THE MUNICIPALITY; EXCEPT AS MODIFIED HEREIN. IN CASE OF CONFLICT, MUNICIPAL CODE SHALL TAKE PRECEDENCE
- B. ALL SANITARY SEWER AND WATERMAIN CONSTRUCTION SHALL CONFORM TO THE STANDARD SPECIFICATIONS FOR WATER AND SEWER MAIN CONSTRUCTION IN ILLINOIS, PUBLISHED JANUARY 2014, AND IN ACCORDANCE WITH THE CODE OF THE MUNICIPALITY; EXCEPT AS MODIFIED HEREIN OR BY ANY PUBLIC AGENCY PERMITS ISSUED FOR THIS WORK. IN CASE OF CONFLICT, THE MORE RESTRICTIVE PROVISIONS SHALL APPLY.
- C. ALL SIDEWALK AND PUBLIC AREAS MUST BE CONSTRUCTED IN ACCORDANCE WITH CURRENT ADA, ILLINOIS HANDICAP ACCESSIBILITY AND ANY APPLICABLE LOCAL ORDINANCES. WHEN CONFLICTS EXIST BETWEEN THE GOVERNING
- D. THE CITED STANDARD SPECIFICATIONS, CODES AND PERMITS, WITH THESE CONSTRUCTION PLANS AND DETAILS, ARE ALL TO BE CONSIDERED PART OF THE CONTRACT. INCIDENTAL ITEMS OR ACCESSORIES NECESSARY TO COMPLETE THIS WORK MAY NOT BE SPECIFICALLY NOTED BUT ARE CONSIDERED A PART OF THIS CONTRACT.

2. UTILITY LOCATIONS

AGENCIES, THE MORE STRINGENT SHALL GOVERN.

1. REFERENCED CODES

- A. THE UTILITY COMPANIES HAVE BEEN CONTACTED IN REFERENCE TO UTILITIES THEY OWN AND OPERATE WITHIN THE LIMITS FOR THIS PROJECT. DATA FROM THESE AGENCIES HAS BEEN INCORPORATED INTO THE PLANS. IT IS, HOWEVER, THE CONTRACTOR'S RESPONSIBILITY TO CONFIRM OR ESTABLISH THE EXISTENCE OF ALL UTILITY FACILITIES AND THEIR EXACT LOCATIONS, AND TO SAFELY SCHEDULE ALL UTILITY RELOCATIONS. FOR ADDITIONAL INFORMATION, THE AGENCIES LISTED ON THIS SHEET MAY BE CONTACTED
- B. THE CONTRACTOR SHALL BE RESPONSIBLE FOR HAVING THE UTILITY COMPANIES LOCATE THEIR FACILITIES IN THE FIELD PRIOR TO CONSTRUCTION AND SHALL ALSO BE RESPONSIBLE FOR THE MAINTENANCE AND PRESERVATION O THESE FACILITIES. THE ENGINEER DOES NOT WARRANT THE LOCATION OF ANY EXISTING UTILITIES SHOWN ON THE PLAN. THE CONTRACTOR SHALL CALL J.U.L.I.E. AT 800-892-0123 AND THE MUNICIPALITY. FOR UTILITY LOCATIONS. THE CONTRACTOR SHALL NOTIFY ALL UTILITY COMPANIES AND THE MUNICIPALITY TWENTY-FOUR (24) HOURS PRIOR
- C. EASEMENTS FOR THE EXISTING UTILITIES, BOTH PUBLIC AND PRIVATE, AND UTILITIES WITHIN PUBLIC RIGHTS-OF-WAY ARE SHOWN ON THE PLANS ACCORDING TO AVAILABLE RECORDS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING THE EXACT LOCATION IN THE FIELD OF THESE UTILITY LINES AND THEIR PROTECTION FROM DAMAGE DUE TO CONSTRUCTION OPERATIONS. IF EXISTING UTILITY LINES OF ANY NATURE ARE ENCOUNTERED WHICH CONFLICT WITH LOCATIONS OF THE NEW CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE OWNER AND ENGINEER SO

3. UTILITY COORDINATION

- A. OWNER SHALL OBTAIN EASEMENTS AND PERMITS NECESSARY TO FACILITATE CONSTRUCTION OF THE PROPOSED UTILITIES. THE CONTRACTOR, HOWEVER, SHALL FURNISH ALL REQUIRED BONDS AND EVIDENCE OF INSURANCE NECESSARY TO SECURE THESE PERMITS
- B. THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING THE NATURE AND STATUS OF ALL UTILITY RELOCATION WORK PRIOR TO THE START OF CONSTRUCTION. THE CONTRACTOR SHALL TAKE APPROPRIATE MEASURES TO ENSURE THAT CONSTRUCTION OPERATIONS DO NOT INTERFERE WITH UTILITY FACILITIES AND RELOCATION WORK. THE SCHEDULE SHOULD REFLECT CONSTRUCTION SEQUENCING WHICH COORDINATES WITH ALL UTILITY RELOCATION WORK. THE CONTRACTOR SHALL BE REQUIRED TO ADJUST THE ORDER OF ITS WORK FROM TIME TO TIME. TO COORDINATE SAME WITH UTILITY RELOCATION WORK. AND SHALL PREPARE REVISED SCHEDULE(S) IN COMPLIANCE THEREWITH AS DIRECTED BY THE OWNER.
- . THE OWNER AND THE ENGINEER SHALL BE NOTIFIED IN WRITING BY THE CONTRACTOR AT LEAST 48 HOURS PRIOR TO THE START OF ANY OPERATION REQUIRING COOPERATION WITH OTHERS. AT&T SHALL BE CONTACTED ONE MONTH PRIOR TO START OF CONSTRUCTION IN ITS UTILITY AREAS. ALL OTHER AGENCIES, UNLESS OTHERWISE NOTED, SHALL BE NOTIFIED IN WRITING BY THE CONTRACTOR TEN (10) DAYS PRIOR TO THE START OF ANY SUCH
- PRIOR TO COMMENCEMENT OF CONSTRUCTION THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS AFFECTING THE WORK WITH THE ACTUAL CONDITIONS AT THE JOB SITE. IN ADDITION, THE CONTRACTOR MUST VERIFY THE ENGINEER'S LINE AND GRADE STAKES. IF THERE ARE ANY DISCREPANCIES WITH WHAT IS SHOWN ON THE CONSTRUCTION PLANS, HE MUST IMMEDIATELY REPORT SAME TO ENGINEER BEFORE DOING ANY WORK, OTHERWISE THE CONTRACTOR ASSUME'S FULL RESPONSIBILITY. IN THE EVENT OF DISAGREEMENT BETWEEN THE CONSTRUCTION PLANS, SPECIFICATIONS AND/OR SPECIAL DETAILS, THE CONTRACTOR SHALL SECURE WRITTEN INSTRUCTION FROM THE ENGINEER PRIOR TO PROCEEDING WITH ANY PART OF THE WORK AFFECTED BY OMISSIONS OR DISCREPANCIES. FAILING TO SECURE SUCH INSTRUCTION, THE CONTRACTOR WILL BE CONSIDERED TO HAVE PROCEEDED AT HIS OWN RISK AND EXPENSE. IN THE EVENT OF ANY DOUBT OR QUESTIONS ARISING WITH RESPECT TO THE TRUE MEANING OF THE CONSTRUCTION PLANS OR SPECIFICATIONS, THE DECISION OF THE ENGINEER SHALL BE FINAL AND CONCLUSIVE.
- ALL PROPOSED ELEVATIONS SHOWN ON THE PLANS ARE FINISHED SURFACE ELEVATIONS, UNLESS OTHERWISE SPECIFIED.
- UPON AWARDING OF THE CONTRACT, AND WHEN REQUIRED BY THE MUNICIPALITY OR OWNER, THE CONTRACTOR SHALL FURNISH A LABOR, MATERIAL AND PERFORMANCE BOND IN THE AMOUNT REQUIRED GUARANTEEING COMPLETION OF THE WORK. THE UNDERWRITER SHALL BE ACCEPTABLE TO THE MUNICIPALITY OR OWNER, AS APPROPRIATE.
- THE CONTRACTORS SHALL PLAN THEIR WORK BASED ON THEIR OWN BORINGS, EXPLORATIONS AND OBSERVATIONS TO DETERMINE SOIL CONDITIONS AT THE LOCATION OF THE PROPOSED WORK. HOWEVER, IF THE OWNER HAS A SOILS REPORT. THE RESULTS WILL BE AVAILABLE FROM THE OWNER UPON WRITTEN REQUEST.
- 8. CONTRACTOR SHALL VIDEO TAPE WORK AREA PRIOR TO CONSTRUCTION FOR THE PURPOSE OF DOCUMENTING EXISTING CONDITIONS.

9. COMMENCING CONSTRUCTION

ACCESS BE DENIED TO ADJACENT PROPERTIES.

- A THE CONTRACTOR SHALL NOTIFY THE OWNER AND/OR HIS REPRESENTATIVE AND THE AFFECTED GOVERNMENTAL AGENCIES IN WRITING AT LEAST THREE FULL WORKING DAYS PRIOR TO COMMENCEMENT OF CONSTRUCTION. IN ADDITION, THE CONTRACTOR SHALL NOTIFY AS NECESSARY, ALL TESTING AGENCIES, EITHER MUNICIPALITY'S OR THE OWNER'S, SUFFICIENTLY IN ADVANCE OF CONSTRUCTION. ALL MATERIAL TESTING SHALL BE THE RESPONSIBILITY AND EXPENSE OF THE CONTRACTOR. THE TESTING AGENCY SHALL MEET THE APPROVAL OF THE OWNER.
- B FAILURE OF CONTRACTOR TO ALLOW PROPER NOTIFICATION TIME WHICH RESULTS IN TESTING COMPANIES TO BE UNABLE TO VISIT SITE AND PERFORM TESTING WILL CAUSE CONTRACTOR TO SUSPEND OPERATION (PERTAINING TO TESTING) UNTIL TESTING AGENCY CAN SCHEDULE TESTING OPERATIONS. COST OF SUSPENSION OF WORK TO BE BORNE BY CONTRACTOR.
- 10. ALL CONTRACTORS SHALL KEEP ACCESS AVAILABLE AT ALL TIMES FOR ALL TYPES OF TRAFFIC. AT NO TIME SHALL
- 11 THE CONTRACTOR SHALL PRESERVE ALL CONSTRUCTION STAKES LINTULTHEY ARE NO LONGER NEEDED. ANY STAKES DESTROYED OR DISTURBED BY THE CONTRACTOR PRIOR TO THEIR USE SHALL BE RESET BY THE DEVELOPER'S ENGINEER
- 12. ANY EXISTING SIGNS, LIGHT STANDARDS AND UTILITY POLES WHICH INTERFERE WITH CONSTRUCTION OPERATIONS AND NOT NOTED FOR DISPOSAL SHALL BE REMOVED AND RESET BY THE CONTRACTOR AT HIS OWN EXPENSE AS SHOWN ON THE ENGINEERING PLANS OR AS DIRECTED BY THE DEVELOPER. ANY DAMAGE TO THESE ITEMS SHALL BE REPAIRED OR REPLACED BY THE CONTRACTOR AT HIS OWN EXPENSE TO THE SATISFACTION OF THE OWNER. ANY SIGNS NOT REQUIRED TO BE RESET. SHALL BE DELIVERED TO THE RESPECTIVE OWNERS.
- REMOVAL OF SPECIFIED ITEMS, INCLUDING BUT NOT LIMITED TO, PAVEMENT, SIDEWALK, CURB, CURB AND GUTTER, CULVERTS, ETC. SHALL BE DISPOSED OF OFF-SITE BY THE CONTRACTOR AT HIS OWN EXPENSE. HE IS RESPONSIBLE FOR ANY PERMIT REQUIRED FOR SUCH DISPOSAL.
- 14. ALL FIELD TILE ENCOUNTERED DURING CONSTRUCTION OPERATIONS SHALL BE CONNECTED TO THE PROPOSED STORM SEWER SYSTEM OR SHALL BE RESTORED TO PROPER OPERATING CONDITION. THE VILLAGE SHALL BE NOTIFIED WHEN A FIELD TILE IS DISCOVERED BEFORE WORK BEGINS A RECORD OF THE LOCATION OF ALL FIELD TILE OR DRAIN PIPE ENCOUNTERED SHALL BE KEPT BY THE CONTRACTOR AND TURNED OVER TO THE ENGINEER. DEVELOPER OR MUNICIPAL ENGINEER UPON COMPLETION OF THE PROJECT. THE COST OF THIS WORK SHALL BE CONSIDERED AS INCIDENTAL TO THE CONTRACT AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- 15. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR SAFETY ON THE JOB.
- 16. THE CONTRACTOR SHALL COLLECT AND REMOVE ALL CONSTRUCTION DEBRIS, EXCESS MATERIALS, TRASH, OIL AND GREASE RESIDUE, MACHINERY, TOOLS AND OTHER MISCELLANEOUS ITEMS WHICH WERE NOT PRESENT PRIOR TO PROJECT COMMENCEMENT AT NO ADDITIONAL EXPENSE TO THE OWNER. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ACQUIRING ANY AND ALL PERMITS NECESSARY FOR THE HAULING AND DISPOSAL REQUIRED FOR CLEAN-UP AS DIRECTED BY THE ENGINEER OR OWNER. BURNING ON THE SITE IS NOT PERMITTED.
- 17. ALL EXISTING UTILITIES OR IMPROVEMENTS, INCLUDING WALKS, CURBS, PAVEMENT AND PARKWAYS DAMAGED OR REMOVED DURING CONSTRUCTION SHALL BE PROMPTLY RESTORED TO THEIR RESPECTIVE ORIGINAL CONDITION. THIS WORK SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT UNLESS SPECIFICALLY NOTED ON THE PLANS.
- 18. TREES NOT MARKED FOR REMOVAL SHALL BE CONSIDERED AS DESIGNATED TO BE SAVED AND SHALL BE PROTECTED UNDER THE PROVISIONS OF (SSRBC) ARTICLE 201.05.
- 19. LIMB PRUNING SHALL BE PERFORMED UNDER THE SUPERVISION OF THE LANDSCAPE ARCHITECT MEETING THE OWNER'S APPROVAL AND SHALL BE UNDERTAKEN IN A TIMELY FASHION SO AS NOT TO INTERFERE WITH CONSTRUCTION.
- 20. ALL LIMBS, BRANCHES, AND OTHER DEBRIS RESULTING FROM THIS WORK SHALL BE DISPOSED OF OFF-SITE BY THE
- ALL CUTS OVER 1" IN DIAMETER SHALL BE MADE FLUSH WITH THE NEXT LARGE BRANCH. WOUNDS OVER 1" IN DIAMETER SHALL BE PAINTED WITH AN APPROVED TREE PAINT

22. GENERAL EXCAVATION/UNDERGROUND NOTES

CONTRACTOR AT HIS OWN EXPENSE OFF-SITE.

- A SLOPF SIDES OF EXCAVATIONS TO COMPLY WITH CODES AND ORDINANCES HAVING JURISDICTION. SHORE AND BRACE WHERE SLOPING IS NOT POSSIBLE FITHER BECAUSE OF SPACE RESTRICTIONS OR STABILITY OF MATERIA EXCAVATED. MAINTAIN SIDES AND SLOPES OF EXCAVATIONS IN A SAFE CONDITION UNTIL COMPLETION OF
- PROVIDE MATERIALS FOR SHORING AND BRACING, SUCH AS SHEET PILING, UPRIGHTS, STRINGERS AND CROSS BRACES, IN GOOD SERVICEABLE CONDITION. PROVIDE MINIMUM REQUIREMENTS FOR TRENCH SHORING AND BRACING O COMPLY WITH CODES AND AUTHORITIES HAVING JURISDICTION. MAINTAIN SHORING AND BRACING IN EXCAVATIONS REGARDLESS OF TIME PERIOD EXCAVATIONS WILL BE OPEN. CARRY DOWN SHORING AND BRACING AS EXCAVATION PROGRESSES IN ACCORDANCE WITH OSHA AND GOVERNING AUTHORITY


- C. PREVENT SURFACE WATER AND SUBSURFACE OR GROUNDWATER FROM FLOWING INTO EXCAVATIONS. REMOVE WATER TO PREVENT SOFTENING OF FOUNDATION BOTTOMS, UNDERCUTTING FOOTINGS, AND SOIL CHANGES DETRIMENTAL TO STABILITY OF SUBGRADES AND FOUNDATIONS. PROVIDE AND MAINTAIN PUMPS, SUMPS, SUCTION AND DISCHARGE LINES AND OTHER DEWATERING SYSTEM COMPONENTS NECESSARY TO CONVEY WATER AWAY FROM EXCAVATIONS. CONVEY WATER REMOVED FROM EXCAVATIONS AND RAINWATER TO COLLECTING OR RUN-OFF AREAS ACCEPTABLE TO AUTHORITIES HAVING JURISDICTION. PROVIDE AND MAINTAIN TEMPORARY DRAINAGE DITCHES AND OTHER DIVERSIONS OUTSIDE EXCAVATION LIMITS FOR EACH STRUCTURE. DO NOT USE TRENCH EXCAVATIONS AS
- D. IMMEDIATELY REPORT CONDITIONS THAT MAY CAUSE UNSOUND BEARING TO THE OWNER/DEVELOPER BEFORE CONTINUING WORK. 23. FINAL ACCEPTANCE
- A. ALL WORK PERFORMED UNDER THIS CONTRACT SHALL BE GUARANTEED BY THE CONTRACTOR AND HIS SURETY FOR A PERIOD OF TWELVE (12) MONTHS FROM THE DATE OF FINAL ACCEPTANCE OF THE PROJECT AND THE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR ALL DEFECTS IN MATERIALS AND WORKMANSHIP OF WHATEVER NATURE DURING THAT PERIOD. THIS GUARANTEE SHALL BE PROVIDED IN THE FORM OF MAINTENANCE BOND IN THE AMOUNT OF 10% OF THE COST OF IMPROVEMENTS
- B. BEFORE ACCEPTANCE BY THE OWNER AND FINAL PAYMENT. ALL WORK SHALL BE INSPECTED BY THE OWNER OR HIS REPRESENTATIVE. FINAL PAYMENT WILL BE MADE AFTER ALL THE CONTRACTOR'S WORK HAS BEEN APPROVED AND
- C. NO UNDERGROUND WORK SHALL BE COVERED UNTIL IT HAS BEEN APPROVED BY THE MUNICIPALITY. APPROVAL TO PROCEED MUST BE OBTAINED FROM THE MUNICIPALITY PRIOR TO INSTALLING PAVEMENT BASE, BINDER, SURFACE, AND PRIOR TO PLACING ANY CONCRETE AFTER FORMS HAVE BEEN SET.
- D. AT THE CLOSE OF EACH WORKING DAY AND AT THE CONCLUSION OF CONSTRUCTION OPERATIONS, ALL DRAINAGE STRUCTURES AND FLOW LINES SHALL BE FREE FROM DIRT AND DEBRIS.

24. UNDERGROUND NOTES

SYSTEMS CONSTRUCTED AS PART OF THIS PROJECT

- A. UNDERGROUND WORK SHALL INCLUDE TRENCHING, INSTALLATION OF PIPE, CASTINGS, STRUCTURES, BACKFILLING OF TRENCHES AND COMPACTION AND TESTING AS SHOWN ON THE CONSTRUCTION PLANS. FITTINGS AND ACCESSORIES NECESSARY TO COMPLETE THE WORK MAY NOT BE SPECIFIED, BUT SHALL BE CONSIDERED AS INCIDENTAL TO THE COST OF THE CONTRACT.
- B. WHERE SHOWN ON THE PLANS OR DIRECTED BY THE ENGINEER, EXISTING DRAINAGE STRUCTURES AND SYSTEMS SHALL BE CLEANED OF DEBRIS AND PATCHED AS NECESSARY TO ASSURE INTEGRITY OF THE STRUCTURE. THIS WORK SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE EACH FOR STRUCTURES AND CONTRACT UNIT PRICE PER LINEAL FOOT FOR SYSTEMS WHICH SHALL BE PAYMENT IN FULL FOR CLEANING PATCHING REMOVAL AND DISPOSAL OF DEBRIS AND DIRT. DRAINAGE STRUCTURES AND SYSTEMS CONSTRUCTED AS PART OF THIS PROJECT SHALL BE MAINTAINED BY THE CONTRACTOR AT HIS EXPENSE. NO PAYMENT WILL BE MADE FOR CLEANING STRUCTURES OR
- C. ANY DEWATERING OF SEWER AND WATER TRENCHES AS WELL AS TEMPORARY SHEETING OR BRACING THAT MAY BE REQUIRED SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR AND SHALL NOT BE CONSIDERED EXTRA WORK UNLESS THERE IS A SPECIFIC LINE ITEM FOR DEWATERING. IN THE EVENT THAT SOFT MATERIALS WITH UNCONFINED COMPRESSIVE STRENGTH LESS THAN 0.5 TSF ARE ENCOUNTERED IN SEWER CONSTRUCTION, THE CONTRACTOR SHALL (LIPON APPROVAL OF THE OWNER AND/OR ENGINEER) OVER-EXCAVATE TO A DEPTH OF ONE (1) FOOT BELOW THE BOTTOM OF THE PIPE AND BACKFILL WITH COMPACTED CRUSHED STONE, PROPERLY FORMED TO FIT THE
- D. TRENCH BACKFILL WILL BE REQUIRED FOR THE FULL TRENCH DEPTH WITHIN TWO (2) FEET OF PROPOSED OR EXISTING PAVEMENTS, UTILITIES, DRIVEWAYS, AND SIDEWALKS AND EXTENDING A DISTANCE EQUAL TO A 1:1 SLOPE FROM SUBGRADE ELEVATION TO TOP OF PIPE. THE TRENCH BACKFILL SHALL CONSIST OF GRANULAR MATERIAL MEETING IDOT CA-6 GRADATION. THE TRENCH BACKFILL SHALL BE COMPACTED IN ACCORDANCE WITH (SSRBC) SPECIFICATIONS. JETTING WITH WATER SHALL NOT BE PERMITTED. THE COST OF SUCH CONSTRUCTION SHALL BE CONSIDERED INCIDENTAL TO THIS CONTRACT AND SHALL BE INCLUDED IN THE UNIT PRICE OF THE PIPE. NO SEPARATE PAYMENT SHALL BE MADE FOR THIS ITEM.
- E. THE CONTRACTOR SHALL INSTALL A 4" X 4" X 8' (NOMINAL) POST AT THE TERMINUS OF THE SANITARY, WATER AND STORM SERVICE, SANITARY AND STORM MANHOLÈS, CATCH BASINS, INLETS AND WATER VAULTS. THE POST SHALL EXTEND 4' ABOVE THE GROUND. THE TOP 12" OF SAID POST SHALL BE PAINTED AS FOLLOWS: SANITARY - RED, WATERMAIN - BLUE, STORM - GREEN.
- F. AFTER THE STORM SEWER SYSTEM HAS BEEN CONSTRUCTED, THE CONTRACTOR SHALL PLACE EROSION CONTROL AT REAR YARD INLET LOCATIONS, AND AT OTHER LOCATIONS SELECTED BY THE ENGINEER, TO MINIMIZE THE AMOUNT OF SILTATION WHICH NORMALLY WOULD ENTER THE STORM SEWER SYSTEM.
- G. HYDRANTS SHALL NOT BE FLUSHED DIRECTLY ON THE ROAD SUBGRADES. WHENEVER POSSIBLE, HOSES SHALL BE USED TO DIRECT THE WATER INTO LOT AREAS OR THE STORM SEWER SYSTEM (IF AVAILABLE). DAMAGE TO THE ROAD SUBGRADE OR LOT GRADING DUE TO EXCESSIVE WATER SATURATION AND/OR EROSION FROM HYDRANT FLUSHING, OR FROM LEAKS IN THE WATER DISTRIBUTION SYSTEM, WILL BE REPAIRED BY THE CONTRACTOR AT HIS COST.
- H. ALL TOP OF FRAMES FOR STORM AND SANITARY SEWERS AND VALVE VAULT COVERS ARE TO BE ADJUSTED TO MEET FINAL FINISH GRADE. THIS ADJUSTMENT IS TO BE MADE BY THE SEWER AND WATER CONTRACTOR AND THE COST IS TO BE CONSIDERED INCIDENTAL. THESE ADJUSTMENTS TO FINISHED GRADE WILL NOT ALLEVIATE THE INTRACTOR FROM ANY ADDITIONAL ADJUSTMENTS AS REQUIRED BY THE MUNICIPALITY UPON FINAL INSPECTION OF THE PROJECT. (FINAL GRADES TO BE DETERMINED BY THE MUNICIPALITY AT THE TIME OF FINAL INSPECTION AND
- I. SLEEVES FOR UTILITY (COMED, TELEPHONE, ETC.) STREET CROSSING, SHALL BE INSTALLED WHERE DIRECTED BY THE OWNER. SLEEVES SHALL BE 6" PVC INSTALLED 36" BELOW THE TOP OF CURB AND EXTEND TWO FEET OUTSIDE THE CURB. TRENCH SHALL BE BACKFILLED WITH COMPACTED GRANULAR MATERIAL.
- J. THE CONTRACTOR SHALL VERIFY THE SIZE AND INVERT ELEVATION OF ALL CONNECTIONS TO AVOID ANY CONFLICTS EFORE STARTING WORK. NOTIFY OWNER OF ANY DISCREPANCIES.
- IT SHALL BE UNDERSTOOD THAT NEITHER THE MUNICIPALITY, ITS OFFICIALS, CONSULTANTS, NOR ITS EMPLOYEES ARE AGENTS OF OR REPRESENTATIVES OF THE OWNER. NONE-THE-LESS. THE MUNICIPALITY TS OFFICIALS AND EMPLOYEES ARE TO BE PROVIDED SAFE ACCESS TO ALL PHASES OF ALL WORK PERFORMED ON THE PROJECT SITE TO MONITOR THE QUALITY OF THE WORK AND ASSURE ITS CONFORMITY WITH THE PLANS AND SPECIFICATIONS. THERE SHALL BE NO PERSONAL LIABILITY UPON ANY OFFICIAL OR EMPLOYEE OF THE MUNICIPALITY ON ACCOUNT OF ACTIONS TAKEN OR NOT TAKEN IN THE COURSE OF THEIR WORK. THE CONTRACTO MUST AT ALL TIMES MAINTAIN A SAFE ACCESS TO THE WORK FOR INSPECTORS. "SAFE": MEANING CONDITIONS COMPLYING WITH ALL PROVISIONS OF ALL APPLICABLE AND RECOGNIZED SAFETY STANDARDS FEDERAL, STATE AND LOCAL. IF ACCESS IS NOT SAFE AND INSPECTIONS CANNOT BE MADE UNDER SAFE CONDITIONS, THE INSPECTOR CAN ORDER CESSATION OF THE WORK SO AFFECTED UNTIL SUCH TIME AS CONTRACTOR PROVIDES SAFE ACCESS.

- 1) 1.5" HMA SURFACE COURSE, MIX "C", N50
- 3.5" HMA BINDER COURSE, IL 19.0, N50 12" AGGREGATE BASE COURSE, TYPE B
- COMPACTED AND STABLE SUBGRADE



TYPICAL SIDEWALK

VILLAGE OF SCHAUMBURG STANDARD ENGINEERING NOTES

VILLAGE OF SCHAUMBURG

DEMOLITION AND RECYCLING REQUIREMENTS Community Development Departmen 101 Schaumburg Court, Schaumburg, IL 60193-1899

SEE SHEET MWRD-GN FOR MWRD GENERAL NOTES

The Village of Schaumburg supports efforts to salvage and reuse materials obtained during the demolition of existing buildings and site improvements as follows:

- May be crushed and reused for fill when meeting the following gradations: Note: Materials shall be approved in writing by Owners Testing Company prior to using under buildings. CA-1 to CA-3 (1"-3"). Use for deeper sub-grade fill under pavement and building slabs;
- construction entrances, similar IDOT permitted uses. CA-7 (1/2"-1"). Use for granular trench backfill in utility trenches, shallow sub-grade fill under pavement and building slabs, similar IDOT permitted uses. CA-6 (1/8"-1"). Use for granular trench backfill in utility trenches, shallow sub-grade fill under pavement and building slabs, lower one-forth of granular base under building slabs or pavements,
- voical IDOT permitted uses. Rubble greater than 4" in size may not be reused on site. • Fences, steel and other metals shall be removed from the site.

trenches (max. 2-3 feet deep) if room for compactor.

Asphalt Pavement: May be pulverized and reused as follows:

- Note: Shall never be used under buildings. Compact in 4" max. lifts. Cannot measure compaction
- with Proctor value (too sticky), have to watch how much its compressing. • Material containing up to 10% large (1/2"-1") particles. Use for backfill in undercut areas, miscellaneous fill areas. • Material containing few particles over ½" in size. Use as subgrade fill under roads, parking lots; use in lieu of bottom 2" of stone base course (compact before placing stone); backfill shallow

- Sewer and water pipes 6' deep or less shall be removed and the trench backfilled with CA-7 or compacted CA-6 aggregate.
- Sewer and water pipes over 6' deep may be removed per above, or completely filled with a flowable fill such as IDOT's Controlled Low Strength Material (CLSM). The CLSM shall be injected into the pipes via access holes or manholes at 300' intervals or closer.
- Sewer Pipes. Crush and remove reinforcing wire. May use for miscellaneous fill or sub-grade fill under pavements. Not under buildings.
- Existing stone base. Clean, no dirt. Use for granular trench backfill in utility trenches, sub-grade fill under pavement, and lower one-forth of granular base under pavements. Not under buildings.
- Topsoil may be stripped and stockpiled as noted on the erosion control plans. Recycled material shall not be used in storm water management facilities.

Village of Schaumburg

Standard Engineering Notes

- The Village of Schaumburg Community Development Department must be notified 48 hours in advance prior to the commencement of work 48 hours in advance prior to each inspection at 847.923.4420. A minimum notice of 5 business days is required from the Engineering and Public Works Department (847.895.7100) for a water main shut down in a business district or commercial area.
- Tree protection fencing must be installed, inspected, and approved prior to the issuance of a Land Development Permit. The fencing must be maintained for the duration of the site work.
- Any temporary or permanent exterior site fencing, including fencing for dumpster enclosures, requires a separate permit from the Community Development Department. Demolition of existing buildings also requires a separate permit from the Community Development Department.
- A separate electrical permit must be obtained from the Community Development Department prior to installing any site lighting or street lighting. The detailed photometrics and exterior light pole locations must be approved by the Engineering Division as part of the land development permit; and the electrical system must be approved by the Building Division as part of the electrical permit for the lighting.
- The Contractor shall indemnify the Village, and their agents, etc. from all liability involved with the construction, installation, testing, and operation of all work associated with this project.
- The Contractor is responsible for having a set of the "Approved" Land Development Permit Plans on the job site during construction. The Contractor is also responsible for making any necessary copies of the "Approved" Land Development Permit Plans for all subcontractors performing site work.
- The Contractor is to verify the location, depth, and invert of all existing utilities and facilities prior to the start of construction. The contractor will be responsible for any damage to existing public or private utilities, or the relocation of any existing utilities to facilitate the installation of the new site work. The contractor must notify the Design Engineer immediately of any discrepancies with the plans and any existing utilities. No work is to be done until the discrepancy is resolved.
- Access to the site, and to within 100 feet of any building, shall be provided for emergency vehicles at all times via a 20 foot wide approved all-weather road. An approved water supply shall be available within 100 feet of any building prior to delivery of any combustible materials to the site.
- No holes are to be left open in the pavement or parkway over any holiday, any weekend, or after 3 P.M. on the day preceding any holiday or any weekend. All existing pavement or concrete to be removed shall be sawcut full-depth along the limits of proposed
- removal before commencement of the pavement removal. 11. All public right-of-way areas that are disturbed during construction shall be restored with 4" of topsoil and sod. Seeding will not be permitted in these areas.

Department of Transportation "Standard Specifications for Road and Bridge Construction" and the

12. All paving, subgrade preparation, curbing, and sidewalk construction shall conform to the Illinois

"Supplemental Specifications and Recurring Special Provisions", latest editions.

13. No asphalt work is allowed between November 1st and April 1st without written permission from the Village.

14. All bituminous concrete used for surface, binder and base courses is to have a Marshall Stability of 1700.

- 15. All concrete work related to the site work shall be IDOT Class SI or Class PV with a compressive strength
- Prior to placing any pavement material, the Contractor is responsible for properly preparing and compacting the subgrade. The required proof-roll must be witnessed by a village inspector. No pavement material is to be placed on wet or soft subgrade. If this condition exists, the Contractor is to stop work and immediately notify the village. No additional pavement work shall be done until the subgrade is corrected.
- All curbs constructed over a utility trench shall be reinforced with two #5 rebars for a length of 20 feet centered over the trench. Sidewalks shall be treated in the same manner using three #5 rebars.
- All sewer and water main construction shall be in conformance with the "Standard Specifications for Water and Sewer Main Construction in Illinois" latest edition.
- The contractor shall not install any sanitary sewer pipe or structures until he has a copy of the permit and permit drawings issued by the Metropolitan Water Reclamation District of Greater Chicago (MWRD) on the job site. This may also apply to storm sewer and/or detention facilities if they are included in the MWRD
- 20. All manholes and valve vaults shall have the "Village of Schaumburg" and "Water", "Storm Sewer" or "Sanitary Sewer" cast into the lid. All open lids or grates shall have the words "Drains to River, Dump no Waste" permanently inscribed. Frames shall be 9" high in paved areas (Neenah R-1713 Neenah R-1772 or approved equal) and 7" high in non-paved areas (Neenah R-1772 or approved equal).
- Band-seal connectors shall be used to join pipes of different materials.

Watershed Management Permit.

- Use CA-6 granular trench backfill, compacted to 95% of Modified Proctor, or CA-7 aggregate, under and within a 1:1 slope from the bottom of all pavements, curbs and sidewalk.
- 23. Any required Best Management Practices (BMP's) shall be installed as shown on the approved land levelopment permit plans. 24. All water main pipe 3" and larger shall be ductile iron pipe Class 52 conforming to ANSI A21.51 with
- cement lining unless otherwise approved by the Village Engineer. All water service lines 2" and smaller shall be Type K copper, unless otherwise noted. 25. All water lines are to be pressure tested and chlorinated per the requirements of the Village of
- maximum depth of 7 feet unless approved by the Director of Engineering and Public Works. Upon completion of the project, the developer shall provide the Village with final "Record Drawings" (1 Mylar reproducible, signed and sealed by the engineer) of all improvements which include the locations and elevations of all mains, services, structures, paved areas, site grading, street and parking lot lights
- and cables, and curbs. Monuments, as specified in Item #27, shall also be shown. Final record drawings must also include a State Plane coordinate system tie-in. In addition to the drawings, electronic files (in PDF format, and DWG or DGN format) of the record drawings must be submitted to the village on CD-

Schaumburg. Also, the minimum cover for all water mains and water service lines is 5.5 feet, with a

All plats 3 acres or larger require concrete monuments complete with the Village of Schaumburg cap and shall be placed at locations to be determined by the Village Engineer. Monuments shall be in accordance with the Subdivision and Land Development Ordinance and shall be shown on the record drawings.

EXISTING	DESCRIPTION	PROPOSED
- >	DRAIN TILE	
->>-	STORM SEWER	->>
->	SANITARY SEWER	_ - >
->>	SANITARY TRUNK SEWER	->>
-w	WATER MAIN (WITH SIZE)	-w 8"-
	PIPE TRENCH BACKFILL	
GG	GAS MAIN	
—тт-	TELEPHONE LINES	
—Е———Е—	ELECTRIC LINE	—Е———Е—
×	FENCE	×
	RIGHT-OF-WAY	
	EASEMENT	
	PROPERTY LINE	
	SETBACK LINE	
	CENTERLINE	
680	CONTOUR	680
©	SANITARY MANHOLE	•
0	STORM MANHOLE	•
Ø	CATCH BASIN	•
	INLET	
q	FIRE HYDRANT	< <
	PRESSURE CONNECTION	•
	PIPE REDUCER	•
Θ	VALVE AND VAULT, VALVE	•
◁	FLARED END SECTION	•
¤	STREET LIGHT	×
-0-	UTILITY POLE	•
A	CONTROL POINT	
þ	SIGN	4
XXX.XX	SPOT ELEVATION	xxx•xx
Φ	SOIL BORING	•
	OVERLAND FLOW ROUTE	-
	DRAINAGE SLOPE	~~ OR →
	- GUARDRAIL	
~~	WATER'S EDGE	~~
	CONCRETE	
	REVERSE PITCH CURB	111111111111111111111111111111111111111
\bigcirc \sim \sim	TREE, FIR TREE, BUSH, &	XX
	PROPOSED TREE TO REMOVE	

LEGEND

<u>ARRKENIA HUNS</u>

M = STORM MANHOLE I = INVERT OR INLET TF = TOP OF FOUNDATIONS = SANITARY MANHOLEGF = GARAGE FLOOR CB = CATCH BASIN

TC = TOP OF CURBTD = TOP OF DEPRESSED CURB

TW = TOP OF RETAINING WALL E = END SECTIONFH = FIRE HYDRANT

T/P = TOP OF PIPEB/P = BOTTOM OF PIPEWM = WATERMAIN

SAN = SANITARY SEWERSTM = STORM SEWERL0 = L00K OUT

BW = BOTTOM OF RETAINING WALL PLO = PARTIAL LOOK OUT

OP = OUTLET OF PIPEGR = GRADE RING (HYDRANT)

		<u>PERMITS</u>		
	DESCRIPTION	LOG NO.	PERMIT NO.	DATE ISSUED
	IEPA NOI			
	IEPA WATER			
	IEPA SANITARY			
	MWRD			
	VILLAGE OF SCHUAMBURG			
	IDNR	231042B		02/17/2023
Г				

CONTACT INFORMATION

VILLAGE ENGINEER

VILLAGE OF SCHAUMBURG 101 SCHAUMBURG COURT SCHAUMBURG, ILLINOIS 60193 (847) 923-4420

LP = LIGHT POLE

VV = VALVE VAULT

ENGINEERING & PUBLIC WORKS 714 S PLUM GROVE ROAD SCHAUMBURG, ILLINOIS 60193 (847) 895-7100 COMED (630) 576-7094

CONTACT: ENG. DEPT. (972) 729-6322 CONTACT: DEAN BOYERS

DISTRICT 1 201 W. SCHAUMBURG COURT

(847) 705-4541

COMCAST 688 INDUSTRIAL DRIVE COMMUNITY DEVELOPMENT DEPT. ELMHURST, ILLINOIS 60126
VILLAGE OF SCHAUMBURG (630) 600-6352 CONTACT: MARTHA GIERAS

> 1000 COMMERCE DRIVE OAK BROOK, IL 60523 (770) 750-6181 CONTACT: JIM EVERETT

NICOR GAS 1844 FERRY ROAD

NAPERVILLE, ILLINOIS 60563 (630) 983-8676 EXT. 2362 CONTACT: CONNIE LANE, P.E.

LEVEL 3 COMMUNICATIONS (877) 366-8344 CONTACT: KEVIN BARBER

WILLOWBROOK, IL 60527 630) 343-2804 CONTACT: JENNIFER DOLMAN WINDSTREAM INC. 30 S. WACKER SUITE 2800 CHICAGO, IL 60606 (319) 790-1514 CONTACT: JOEL SCHROEDER

WEST SHORE PIPE LINE CO (630) 407-6800

CONTACT: BETH AUMAN

G4S TECHNOLOGY LLC

565 WILLOWBROOK CENTRE PARKWA

FILENAME: 13379GN


JOB NO.

OF 21


N:\Projects 13000-13999\13379\ENG\13379GN01.dgn Default User=bmcgovern


DATE: 10/18/24

13379 SHEET



N:\Projects 13000-13999\13379\ENG\13379ET.dgn Default User=bmcgovern





<u> </u>	STORM SEWER
	SANITARY SEWER
	COMBINED SEWER
——	WATER MAIN GAS MAIN
—	UNDERGROUND TELEPHONE LINE
——E———E——	
CATV	UNDERGROUND CATV LINE
— он — он —	OVERHEAD WIRE(S) ON UTILITY POLES
— F0 — F0 —	FIBER OPTIC LINE
	RAILROAD
X	FENCE GUARDRAIL
	EDGE OF WATER
\psi \psi	WETLAND LIMITS
	AIR CONDITIONING UNIT
	BOLLARD HAND HOLE
	TRAFFIC SIGNAL BOX
]	TRAFFIC SIGNAL ELECTRIC METER
¤	LIGHT POLE GUY WIRE ANCHOR
⊙ —	LANDSCAPE LIGHT/FLOOD LIGHT
- -	UTILITY POLE
E E	ELECTRIC PEDESTAL ELECTRIC MANHOLE
	TELEPHONE PEDESTAL
	TELEPHONE MANHOLE
	CABLE PEDESTAL
	CABLE MANHOLE GAS METER
6	GAS VALVE
© ©	GAS MANHOLE COMBINATION MANHOLE
	SANITARY MANHOLE
© ©	GREASE TRAP CLEANOUT
8	DOWNSPOUT
<u> </u>	STORM MANHOLE CULVERT
	CATCH BASIN
\Box	FLARED END SECTION
=	INLET AUXILIARY VALVE
®	BUFFALO BOX SIAMESE CONNECTION/AUTO SPRINKLER
b → Oôrd® K®	WATER VALVE
ğ	FIRE HYDRANT WATER METER
8	WELL VALVE AND VAULT
\bigcirc	MAILBOX
 <u> 0</u>	SIGN
©©©©<	FLAG POLE SATELLITE DISH
	UNIDENTIFIED PEDESTAL
(P)	VENT PIPE UNIDENTIFIED MANHOLE
	STONE
⊠ •	RIGHT OF WAY MONUMENT PK NAIL/MAG NAIL
▼	RAILROAD SPIKE IRON ROD
0 ×	IRON PIPE CROSS
× ⊡	CRUSS CONCRETE MONUMENT
⊙	DISC
→	BORING
-	TEST PIT
120	
(012)	TREE WITH SIZE
(12)	FIR TREE WITH SIZE
AIL.	PURU.
(BUSH
	WINDOW WELL
	ASPHALT
Δ	CONCRETE
0.0000000000000000000000000000000000000	GRAVEL
70000 107050	BRICK
	CONTOUR

UNDERGROUND UTILITIES ARE SHOWN BY USING PHYSICAL EVIDENCE FOUND ON THE SURFACE AND/OR FROM UTILITY
COMPANY FIELD STAKES AND, THEREFORE, THEIR LOCATIONS
ARE APPROXIMATE AND SUSPECTED AND MAY NOT BE COMPLETELY ACCURATE. FOR MORE ACCURATE LOCATION,

PIPE FLOW DIRECTIONS, IF SHOWN, ARE BASED ON FIELD INVERT ELEVATIONS UNLESS EXISTING PLANS INDICATE OTHERWISE, IN WHICH CASE THE EXISTING PLAN FLOW

SOURCE BENCHMARK: VILLAGE OF SCHAUMBURG BENCHMARK MONUMENT STATION NUMBER: 1274 STATION NOMBER. 1274
SET ALUMINUM DISK AT THE N.E. CORNER OF LOT 1 OF
PATRICK BMW & MINI PLAT OF CONSOLIDATION RECORDED
OCT. 13, 2009 AS DOC. 0928644050.

BOX W/ CROSS CUT ON THE S.W. CORNER OF THE CONC. SLAB WITH A C.E. TRANS. LOCATED ON THE W. SIDE OF MAIN


SITE BENCHMARK #2: ARROW BOLT ON THE 1ST FIRE HYDRANT S. OF THE N.E.

SITE BENCHMARK #3: N.E. BOLT OF THE 1ST FIRE HYDRANT E. OF THE S.W. PROPERTY CORNER. ELEVATION = 762.17 NAVD88

FILENAME: 13379ET

DATE 10/18/24

JOB NO. 13379 SHEET




N:\Projects 13000-13999\13379\ENG\13379DEMO.dgn Default User=bmcgovern

UMBURG ROHRM SCHAUMBURG, ILLINOIS H

FILENAME: 13379DEMO

10/18/24

JOB NO.



N:\Projects 13000-13999\13379\ENG\13379GM01.dgn Default User=bmcgovern

CH/


FILENAME: 13379GM01

DATE

10/18/24

JOB NO. 13379

SHEET




N:\Projects 13000-13999\13379\ENG\13379GR01.dgn Default User=bmcgovern

FILENAME:

13379GR01

DATE: 10/18/24

13379 SHEET



N:\Projects 13000-13999\13379\ENG\13379UT01.dgn Default User=bmcgovern

I

FILENAME:

This Soil Erosion & Sediment Control (SESC) Plan has been prepared to fulfill one of the requirements

of the National Pollutant Discharge Elimination System (NPDES) General Permit No. ILR10

1) The practices selected for implementation were determined on the basis of technical guidance contained in IEPA's Illinois Urban Manual, Federal, State, and/or Local Requirements. The storm water management - detention basins (wet basins, dry basins, vaults, etc.) storm sewers 2) Velocity dissipation devices, such as rip-rap aprons at flared end sections or level spreaders, shall be placed at discharge locations and along the length of any outfall channel as necessary to provide a non-erosive velocity flow from the structure to a watercourse so that the natural, physical, and biological characteristics and functions are maintained and protected (e.g., maintenance of hydrologic conditions, such as the hydroperiod and hydrodynamics present prior to the initiation of construction activities). E. Waste Management Solid waste materials including trash, construction debris, excess construction materials, machinery, tools and other items will be collected and disposed of off site by the contractor. The contractor is responsible to acquire the permit required for such disposal. Burning on site will not be permitted. No solid materials, including building materials, shall be discharged to Waters of the State, except as authorized by a Section 404 permit. All waste materials should be collected and stored in approved receptacles. No wastes should be placed in any location other than in the approved containers appropriate for the materials being discarded. There should be no liquid wastes deposited into dumpsters or other containers which may leak. Receptacles with deficiencies should be replaced as soon as possible and the appropriate clean-up procedure should take place, if necessary. Construction waste material is not to be buried on site. Waste disposal should comply with all Local, State, and Federal regulations. On-site hazardous material storage should be minimized and stored in labeled, separate receptacles from non-hazardous waste. All hazardous waste should be disposed of in the manner specified by Local or State regulation or by the F. Concrete Waste Management Concrete waste or washout should not be allowed in the street or allowed to reach a storm water drainage system or watercourse. When practicable, a sign should be posted at each location to identify the washout. To the extent practicable, concrete washout areas should be located a reasonable distance from a storm water drainage inlet or vatercourse, and should be located at least 10 feet behind the curb, if the washout area is adjacent to a paved road. A stabilized entrance that meets Illinois Urban Manual standards should be installed at each washout area. The containment facilities should be of sufficient volume to completely contain all liquid and concrete waste materials including enough capacity for anticipated levels of rainwater. The dried concrete waste material should be picked up and disposed of properly when 66% capacity is reached. Hardened concrete can be properly recycled and used again on site (as approved by the Engineer) or hauled off site to an appropriate landfill. G. Concrete Cutting Concrete waste management should be implemented to contain and dispose of saw-cutting slurries. Concrete cutting should not take place during or immediately after a rainfall event. Waste generated from concrete cutting should be cleaned-up and disposed into the concrete washout facility as described above. H. Vehicle Storage and Maintenance When not in use, construction vehicles should be stored in a designated area(s) outside of the regulatory floodplain, away from any natural or created watercourse, pond, drainage-way or storm drain. Controls should be installed to minimize the potential of runoff from the storage area(s) from reaching storm drains or water courses. Vehicle maintenance (including both routine maintenance as well as on-site repairs) should be made within a designated area(s) to prevent the migration of mechanical fluids (oil, antifreeze, etc.) into watercourses, wetlands or storm drains. Drip pans or absorbent pads should be used for all vehicle and equipment maintenance activities that involve grease, oil, solvents, or other vehicle fluids. Construction vehicles should be inspected frequently to identify any leaks; leaks should be repaired immediately or the vehicle should be removed from site. Dispose of all used oil, antifreeze, solvents and other vehicle-related chemicals in accordance with United States Environmental Protection Agency (USEPA) and IEPA regulations and per Material Safety Data Sheet (MSDS) and/or manufacturer instructions. Contractors should immediately report spills to the Primary Contact. I. Material Storage and Good Housekeeping Materials and/or contaminants should be stored in a manner that minimizes the potential to discharge into storm drains or watercourses. An on-site area should be designated for material delivery and storage. All materials kept on site should be stored in their original containers with legible labels, and if possible, under a roof or other enclosure. Labels should be replaced if damaged or difficult to read. Bermed-off storage areas are an acceptable control measure to prevent contamination of storm water. MSDS should be available for referencing clean-up procedures. Any release of chemicals/contaminants should be immediately cleaned up and disposed of properly. Contractors should immediately report all spills to the Primary Contact, who should notify the appropriate agencies, if needed To reduce the risks associated with hazardous materials on site, hazardous products should be kept in original containers unless they are not re-sealable. The original labels and MSDS should be retained on site at all times. Hazardous materials and all other material on site should be stored in accordance with manufacturer or MSDS specifications. When disposing of hazardous materials, follow manufacturer or Local and State recommended methods. The following good housekeeping practices should be followed on site during the construction - An effort should be made to store only enough product required to do the job. - All materials stored on site should be stored in a neat, orderly manner in their appropriate containers and adequately protected from the environment - Products should be kept in their original containers with the original manufacturer's label. Operations should be observed as necessary to ensure proper use and disposal of materials - Whenever possible, all of a product should be used up before disposing of the container. - Manufacturer's recommendations for proper use and disposal should be followed. J. Management of Portable Sanitary Stations To the extent practicable, portable sanitary stations should be located in an area that does not drain to any protected natural areas, Waters of the State, or storm water structures and should be anchored to the ground to prevent from tipping over. Portable sanitary stations located on impervious surfaces should be placed on top of a secondary containment device, or be surrounded by a control device (e.g., gravel-bag berm). The contractor should not create or allow unsanitary conditions. Sanitary waste should be disposed of in accordance with applicable State and/or K. Spill Prevention and Clean-Up Procedures Manufacturer's recommended methods for spill clean-up should be available and site personnel should be made aware of the procedures and the location of the information and clean-up supplies. Materials and equipment necessary for spill clean-up should be kept in the material storage area on site. Equipment and materials should include, but are not limited to, brooms, dust pans, mops, rags, gloves goggles, kitty litter, sand, sawdust and plastic and/or metal trash containers specifically for this purpose. Discharges of a hazardous substance or oil caused by a spill (e.g., a spill of oil into a separate storm sewer or Waters of the State) are not authorized by the ILR10 permit. If a spill occurs, notify the Primary Contact immediately. The construction site should have the capacity to control, contain, and remove spills, if they occur. Spills should be cleaned up immediately (after discovery) in accordance with MSDS and should not be buried on site or washed into storm sewer drainage inlets, drainage-ways, or Waters of the State. Spills in excess of Federal Reportable Quantities (as established under 40 CFR Parts 110, 117, or 302), should be reported to the National Response Center by calling (800) 424-8802. MSDS often include information on Federal Reportable Quantities for materials. Spills of toxic or hazardous materials should be reported to the appropriate State or Local government agency, as required. When cleaning up a spill, the area should be kept well ventilated and appropriate personal protective equipment should be used to minimize injury from contact with a hazardous substance. In addition to the good housekeeping and other management practices discussed in the previous sections of these Notes. the following minimum practices should be followed to reduce the risk of spills: - On-site vehicles should be monitored for leaks and should receive regular preventative maintenance to reduce the Petroleum products should be stored in tightly sealed and clearly labeled containers. Contractors should follow the manufacturer's recommendations for proper use, storage, and disposal of materials. Excess materials should be disposed of according to the manufacturer's instructions or State and Local regulations, and should not be discharged to the storm sewer or waterbody. L. De-Watering Operations During de-watering/pumping operations, only uncontaminated water should be allowed to discharge to protected natural areas, Waters of the State, or to a storm sewer system (in accordance with Local permits). Inlet hoses should be placed in a stabilized sump pit or floated at the surface of the water in order to limit the amount of sediment intake. Pumping operations may be discharged to a stabilized area that consists of an energy dissipating device (e.g., stone), sediment filter bag, or both. Adequate erosion controls should be used during de-watering operations as necessary. Stabilized conveyance channels should be installed to direct water to the desired location as applicable. Additional control measures may be installed at the outlet area at the discretion of the Primary Contact or Engineer. M. Off-Site Vehicle Tracking The site should have one or more stabilized construction entrances in conformance with the Plan details. Stabilized construction entrance(s) should be installed to help reduce vehicle tracking of sediments. Streets should be swept as needed to reduce excess sediment, dirt, or stone tracked from the site. Maintenance may include top dressing the stabilized entrance with additional stone and removing top layers of stone and sediment, as needed. Vehicles hauling erodible material to and from the construction site should be covered with a tarp. N. Topsoil Stockpile Management If topsoil is to be stockpiled at the site, select a location so that it will not erode, block drainage, or interfere with work on site. Topsoil stockpiles should not be located in the 100-year floodplain or designated buffer protecting Waters of the State. During construction of the project, soil stockpiles should be stabilized or protected with sediment trapping measures. Perimeter controls, such as silt fence, should be placed around the stockpile immediately. Stabilization of the stockpile should be completed if the stockpile is to remain undisturbed for longer than fourteen days. Dust control should be implemented on site as necessary. Repetitive treatment should be applied as needed to

accomplish control when temporary dust control measures are used. A water truck should be present on site (or available) for sprinkling/irrigation to limit the amount of dust leaving the site. Watering should be applied daily (or more frequently) to be effective. Caution should be used not to overwater, as that may cause

If field observations indicate that additional protection from wind erosion (in addition to, or in place of

approval of the Engineer and/or Primary Contact.

watering) is necessary, alternative dust suppressant controls should be implemented at the discretion and

Street cleaning should also be used as necessary to control dust. Paved areas that have soil on them from the construction site should be cleaned as needed, utilizing a street sweeper or bucket-type endloader or scraper at the direction of the Engineer and/or Primary Contact. 3. MAINTENANCE Maintenance of the controls incorporated into this project should be performed as needed to assure their con effectiveness. This includes prompt and effective repair and/or replacement of deficient control measures. following is a description of procedures that should be used to maintain, in good and effective operating cond erosion and sediment control measures and other protective measures identified in the SESC Plan and Standa Dust control: When temporary dust control measures are used, repetitive treatment should be applied as need Sediment filter bags: Sediment filter bags should be installed on pump outlet hoses that discharge off site or sensitive on-site areas, and should be placed in an area that allows for the bag to be removed without produc a sediment discharge. The bags should be inspected frequently and repaired or replaced as needed. Silt fence: Silt fences should be inspected regularly for undercutting where the fence meets the ground, over and tears along the length of the fence. Deficiencies should be repaired immediately. Remove accumulated from the fence base when the sediment reaches one-half the fence height. During final stabilization, properly of any sediment that has accumulated on the silt fence. Alternative sediment control measures should be co for areas where silt fence continually fails. Stabilized construction entrance: The stabilized construction entrances should be maintained to prevent track sediment onto public streets. Maintenance includes top dressing with additional stone and removing top layer stone and sedlment. The sedlment tracked onto the public right-of-way should be removed immediately. Temporary sediment traps: Temporary sediment traps should be inspected after each period of significant rai Remove sediment and restore the trap to its original dimensions when the sediment has accumulated to one-f design depth of the permanent pool. Place the sediment that is removed in a designated disposal area. Chec structure for damage from erosion or piping. After all sediment-producing areas have been permanently stab remove the structure and all unstable sediment. Grade the area to blend with the adjoining areas and stabilize 4. INSPECTIONS The Permittee (or their authorized representative) will be responsible for conducting site inspections in compliance with the ILR10 NPDES Permit. After each inspection, a report should be prepared by the qualified personnel who performed the inspection. The inspection report should be maintained on site Inspections should be conducted at least once every seven calendar days and within 24 hours or by the end of the following work day, of the end of a storm event that is 0.5 inches or greater, or equivalent snowfall. Inspections may be reduced to once per month when construction activities have ceased due to frozen condit Weekly Inspections will recommence when construction activities are conducted, or if there is 0.5" or greater event, or a discharge due to snowmelt occurs. Each inspection should include the following components: A. Disturbed areas and areas used for the storage of materials that are exposed to precipitation should be inspected for evidence of, or the potential for, pollutants entering the drainage system. The erosion and sediment control measures identified in the SWPPP should be observed to ensure that they have been installed and are operating correctly. Where discharge points are accessible they should be inspected to ascertain whether erosion control measures are effective in preventing significant impacts to the receiving waters. Locations where vehicles enter or exit the site should be inspected for off-site sediment tracking. All pumping operations and other potential non-storm water discharge sources should also be inspected. B. Based on the results of the inspection, the description of potential pollutant sources identified, and the pollution prevention measures described in the SWPPP should be revised, as appropriate, as soon as practicable after the inspection. The modifications, if any, shall provide for timely implementation of any changes to the SWPPP within 7 calendar days following the inspection C. A report summarizing the scope of the inspection, name(s) and qualifications of personnel making the inspection, the date(s) of the inspection, major observations relating to the implementation of the SWPPP, and actions taken in accordance with paragraph B. above should be made and retained as part of the SWPPP for at least three years from the date that permit coverage expires or is terminated The report shall be signed in accordance with Part VI.G. (Signatory Requirements) of the ILR10 NPDES Permit D. The Permittee shall notify the appropriate agency field operations section office by e-mail at: epa.swnoncomp@illinois.gov . telephone or fax within 24 hours of any incidence of noncompliance for any iolation of the storm water pollution prevention plan observed during any inspection conducted or for violation of any condition of this permit. The Permittee should complete and submit within 5 days an "Incidence of Non-Compliance" (ION) report for any violation of the SWPPP observed during an inspection conducted, including those not required by the SWPPP. Submission should be on forms provided by IEPA and include specific information on the cause of non-compliance, actions which were taken to prevent any further causes of non-compliance, and a statement detailing any environmental impact, which may have result E. All reports of non-compliance shall be signed by a responsible authority as defined in Part VI.G. (Signatory Requirements), of the ILR10 NPDES Permit. F. After the initial contact has been made within the appropriate agency field operations section office, all reports of non-compliance shall be mailed to IEPA at the following address: Illinois Environmental Protection Agency Division of Water Pollution Control Compliance Assurance Section 1021 North Grand Avenue East Post Office Box 19276 Springfield, Illinois 62794-9276 5. NON-STORM WATER DISCHARGES Except for flows from fire fighting activities, possible sources of non-storm water that may be combined with storm water discharges associated with the proposed activity, are described below Fire hydrant flushings Water used to wash vehicles where detergents are not used Water used to control dust Potable water sources including uncontaminated waterline flushings Landscape irrigation drainages Routine external building washdown which does not use detergents Pavement wash waters where spills or leaks of toxic or hazardous materials have not occurred (unless spilled materials have been removed) and where detergents have not been used. Uncontaminated air conditioning condensate Irrigation ditches Uncontaminated ground water Foundation or footing drains where flows are not contaminated with process materials such as solvents 6. PROHIBITED NON-STORMWATER DISCHARGES Concrete and wastewater from washout of concrete (unless managed by an appropriate control) Drywall compound Wastewater from washout and cleanout of stucco, paint Form release oils Curing compounds and other construction materials Fuels, oils, or other pollutants used in vehicle or equipment operation and maintenance Soaps, solvents, or detergents Toxic or hazardous substances from a spill or other release Any other pollutant that could cause or tend to cause water pollution Pollution prevention measures should be implemented for non-storm water components of the discharge. CONTRACTOR CERTIFICATION I CERTIFY UNDER PENALTY OF LAW THAT I UNDERSTAND THE TERMS AND CONDITIONS OF THE GENERAL NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT (ILR10 THAT AUTHORIZES THE STORM WATER DISCHARGES ASSOCIATED WITH INDUSTRIAL ACTIVITY FROM THE CONSTRUCTION SITE IDENTIFIED AS PART OF THIS CERTIFICATION.

TELEPHONE NUMBER

ALL CONTRACTORS PERFORMING WORK ON THIS SITE ARE REQUIRED TO SIGN A CONTRACTOR CERTIFICATION

STATEMENT AS ILLUSTRATED ABOVE. THE SIGNED STATEMENTS WILL BE MAINTAINED ON THE SITE WITH THE

CONTRACTOR SIGNATURE

PRINTED NAME & TITLE

STREET ADDRESS

CITY, STATE, ZIP CODE

TRADE/ RESPONSIBILITIES:_

NAME OF CONTRACTING FIRM

itinued Fhe dition, ard		
eded to		
to cing		
topping, sediments dispose nsidered		
king of ers of		
infall. half the ck the illized, e		
of		
tions. raln		
t.		
lted		
iteu		
		 OL
		OL NA NL

STABILIZATION TYPE	JAN.	FEB.	MAR.	APR.	MAY	JUNE	JULY	AUG.	SEPT.	OCT.	NOV.	DEC
PERMANENT SEEDING			+ <u>A</u>			*	*					
DORMANT	В										В	
SEEDING											7	
TEMPORARY SEEDING			+ <u>C</u>			_	D		_			
SODDING			+ E**									
	F											,
MULCHING												
			JEGRASS 90 RENN I AL R		<u> </u>	С	SPRIN	G OATS 10	0 LBS/ACRI	E	L	ı

1 PERENNIAL RYEGRASS 30 LBS/ACRE.

D WHEAT OR CEREAL RYE

SOD

150 LBS/ACRE.

B KENTUCKY BLUEGRASS 135 LBS/ACRE MIXED WITH PERENNIAL RYEGRASS 45 LBS/ACRE + STRAW MULCH 2 TONS/ACRE.

F STRAW MULCH 2 TONS/ACRE. * IRRIGATION NEEDED DURING JUNE AND JULY.

** IRRIGATION NEEDED FOR 2 TO 3 WEEKS AFTER APPLYING SOD. SOIL PROTECTION CHART

Village of Schaumburg

EROSION AND SEDIMENT CONTROL NOTES

1. All erosion and sediment control measures are to be constructed and maintained in accordance with the Illinois Urban Manual, latest edition.

2. All erosion and sediment control measures shall be installed prior to the start of any construction or disturbance of the site. The measures may have to be adjusted to meet field conditions during construction. Any measures, in addition to those outlined in the plans and which are deemed necessary by the village, shall be implemented immediately by the developer.

3. Regular inspection and maintenance of all erosion and sediment control measures must be provided by the developer. Inspections should occur weekly, and after any rainfall greater than 1/2". Any non-functioning sediment control measures or damaged devices that are found during inspection shall be repaired or replaced immediately The developer shall be responsible for any sediment which leaves the property, and the developer is also responsible for maintenance of all sediment control measures until the site is permanently stabilized.

4. All points of construction ingress and egress shall be protected to prevent tracking of debris, dirt, and mud onto adjacent streets, parking lots, or properties. Any debris, dirt, or mud that reaches an improved public right-of-way, street, or parking area shall be promptly removed, and transported to a proper disposal area.

5. All sediment must be prevented from entering any public or private storm drainage system. Reusable inlet filter baskets (Flexstorm, CatchAll, or equivalent), sediment basins, and water filtering bags, shall be provided as needed.

6. All drainage swales shall be sodded. Areas or embankments having slopes steeper than or equal to 3H:1V, and approved by the village, shall be stabilized with sod, matting, or erosion blanket in combination with appropriate seeding.

7. Topsoil stockpiles shall be located to avoid erosion of stockpile onto neighboring properties or into restored project areas. Stockpiles shall be located so that a drainage swale is located between the stockpile and any downstream properties. If a stockpile is to remain in place for more than 14 days, it must be seeded and blanketed to minimize soil erosion by both wind and water.

8. The developer is responsible for obtaining a separate National Pollution Discharge Elimination System (NPDES)

permit from the Illinois Environmental Protection Agency whenever 1 acre or more of property is disturbed. For developments over 1 acre, the developer must also prepare and maintain a Storm Water Pollution Prevention Plan

(SWPPP) at the project site, along with the NPDES permit. For developments less than 1 acre, a Sediment and Erosion Control Plan must be maintained by the developer.

9. Disturbed areas shall be stabilized with temporary or permanent measures within 14 calendar days of the end of active hydrologic disturbance, or redisturbance.

10. If dewatering services are used, adjacent properties and discharge locations shall be protected from erosion. Discharges from construction dewatering shall be routed through an effective sediment control measure such as a sediment trap, a sediment basin, or any other appropriate measure.

OUTFALL NAME OR NUMBER	INLET PIPE SIZE d (IN)	VELOCITY (F/S)	LENGTH OF APRON L (FT)	RIPRAP GRADATION	WIDTH OF APRON U/S FACE 3d (FT)	WIDTH OF APRON D/S FACE 3d+L (FT)	DEPTH OF RIPRAP Y (IN)

PROJECT:
PERMIT #: ILR10
I CERTIFY UNDER PENALTY OF LAW THAT THIS DOCUMENT AND ALL ATTACHMENTS WERE PREPARED UNDER MY DIRECTION OR SUPERVISION IN ACCORDANCE WITH A SYSTEM DESIGNED TO ASSURE THAT QUALIFIED PERSONNEL PROPERLY GATHERED AND EVALUATED THE INFORMATION SUBMITTED. BASED ON MY INQUIRY OF THE PERSON OR PERSONS WHO MANAGE THE SYSTEM, OR THOSE PERSONS DIRECTLY RESPONSIBLE FOR GATHERING THE INFORMATION, THE INFORMATION IS, TO THE BEST OF MY KNOWLEDGE AND BELIEF, TRUE, ACCURATE, AND COMPLETE. I AM AWARE THAT THERE ARE SIGNIFICANT PENALTIES FOR SUBMITTING FALSE INFORMATION, INCLUDING THE POSSIBILITY OF FINE AND IMPRISONMENT FOR KNOWING VIOLATIONS.
SIGNATURE OF OWNER DATE
PRINTED NAME OF OWNER

THE CERTIFICATION ILLUSTRATED ABOVE SHALL BE SIGNED BY THE OWNER LISTED ON THE NOTICE OF INTENT IN ACCORDANCE WITH PART VI.G. OF THE ILR10 NPDES PERMIT. THE SIGNED STATEMENT SHALL BE MAINTAINED

OUTFALL NAME OR NUMBER	INLET PIPE SIZE d (IN)	VELOCITY (F/S)	LENGTH OF APRON L (FT)	RIPRAP GRADATION	WIDTH OF APRON U/S FACE 3d (FT)	WIDTH OF APRON D/S FACE 3d+L (FT)	DEPTH OF RIPRAP Y (IN)
	OWNER SWPPP CE	ERTIFICATION					
	PERMIT #: ILR1	0					

N:\Projects 13000-13999\13379\ENG\13379SE1.dgn Default User=bmcgovern

- permanent seeding

- erosion control blanket

Site-specific scheduling of the implementation of these practices is included in the Soil Protection Chart.

Stabilization of disturbed areas must be initiated within 1 working day of permanent or temporary cessation of earth

activities and shall be completed as soon as possible but not later than 14 days from the initialization of stabilization

a. Where the initiation of stabilization measures is precluded by snow cover, stabilization measures shall be

b. On areas where construction activity has temporarily ceased and will resume after 14 days, a temporary

ollutants from exposed areas of the site. Structural practices should be placed on upland soils to the degree practicable.

2) Structural Practices - Provided below is a description of structural practices that should be implemented, to the

degree attainable to divert flows from exposed soils, store flows or otherwise limit runoff and the discharge of

Provided below is a description of measures that will be installed during the construction process to control

the pollutants in storm water discharges that will occur after the construction operations have been completed.

The installation of these devices may be subject to Section 404 of the Clean Water Act.

stabilization method can be used. Temporary stabilization techniques and materials shall conform to the SWPPP.

A record of the dates when major grading activities occur, when construction activities cease on a

portion of the site, and when stabilization measures are initiated should be included in the SWPP

The installation of the following devices may be subject to Section 404 of the Clean Water Act:

work in an area. Exceptions to these time frames are specified below.

initiated as soon as practicable,

- stabilized construction entrance


silt fence


D. Storm Water Management

FILENAME: 13379SPECS2 DATE: 10/18/24

JOB NO. 13379

SHEET





N:\Projects 13000-13999\13379\ENG\13379SE3.dgn Default User=bmcgovern

- THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" ADOPTED APRIL. 1, 2016, THE MOST RECENT EDITION OF THE "STANDARD SPECIFICATIONS FOR WATER AND SEWER MAIN CONSTRUCTION IN ILLINOIS", AND REVISIONS THERETO, THESE IMPROVEMENT PLANS AND DETAILS, SPECIAL PROVISIONS AND CODES AND ORDINANCES OF THE VILLAGE OF SCHAUMBURG, "INTROCE SHALL COVERN APPLICABLE PORTIONS OF THIS PROJECT.

 28. THE ENGINEER AND VILLAGE ARE NOT RESPONSIBLE FOR THE CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES OR PROCEDURES, TIME OF PERFORMANCE, PROGRAMS OR FOR ANY SAFETY PRECAUTIONS USED BY THE CONTRACTOR. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR EXECUTION OF HIS WORK IN ACCORDANCE WITH THE CONTRACT DOCUMENTS AND
- THE CONTRACTOR SHALL OBTAIN, ERECT, MAINTAIN AND REMOVE ALL SIGNS, BARRICADES, FLAGMEN AND OTHER CONTROL DEVICES AS MAY BE NECESSARY FOR THE PURPOSE OF REGULATING, WARNING OR GUIDING TRAFFIC. PLACEMENT AND MAINTENANCE OF ALL TRAFFIC CONTROL DEVICES SHALL BE IN ACCORDANCE WITH THE APPLICABLE PARTS OF ARTICLE 107.14 OF THE STANDARD SPECIFICATIONS, THE "STANDARD SPECIFICATIONS FOR TRAFFIC CONTROL TEMPS"
- 3. LOCATION OF UTILITIES SHOWN ON PLANS ARE APPROXIMATE ONLY, AND ARE NOT NECESSARILY COMPLETE. CONTRACTOR SHALL MAKE HIS OWN NOT NECESSARILY COMPLETE. CONTRACTOR SHALL MAKE HIS OWN INVESTIGATIONS AS TO LOCATION OF ALL EXISTING UNDERGROUND STRUCTURES, CABLES, UTILITIES AND PIPE LINES.
- 4. IF EXISTING UTILITY LINES OF ANY NATURE ARE ENCOUNTERED WHICH CONFLICT IN LOCATION WITH NEW CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE ENGINEER AND VILLAGE SO THAT THE CONFLICT MAY BE RESOLVED.
- 5. THE CONTRACTOR SHALL NOTIFY J.U.L.I.E. (1-800-892-0123) AT LEAST TEN DAYS PRIOR TO CONSTRUCTION SO REQUIRED PROTECTION OF ALL ROADWAYS, STRUCTURES, POLES, CABLES AND PIPE LINES, BEFORE CONSTRUCTION THAT EACH UTILITY COMPANY CAN STAKE OUT ANY UNDERGROUND IMPROVEMENTS THAT THEY MAY HAVE WHICH MIGHT INTERFERE WITH THE PROPOSED
- 6. THE CONTRACTOR SHALL BE REQUIRED TO MAKE ARRANGEMENTS FOR THE PROPER BRACING, SHORING AND OTHER REQUIRED PROTECTION OF ALL ROADWAYS, STRUCTURES, POLES, CABLES AND PIPE LINES, BEFORE CONSTRUCTION BEGINS. HE SHALL BE RESPONSIBLE FOR ANY DAMAGE TO THE STREETS OR ROADWAYS AND ASSOCIATED STRUCTURES AND SHALL MAKE REPAIRS AS NECESSARY TO THE SATISFACTION OF THE ENGINEER AND VILLAGE AT HIS OWN EXPENSE.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL PRIVATE AND PUBLIC UTILITIES EVEN THOUGH THEY MAY NOT BE SHOWN ON THE PLANS. ANY UTILITY THAT IS DAMAGED DURING CONSTRUCTION SHALL BE REPAIRED ON REPLACED TO THE ENGINEER AND VILLAGE BY THE CONTRACTOR AT HIS OWN EXPENSE.
- THE CONTRACTOR SHALL EXAMINE THE PLANS AND SPECIFICATIONS, VISIT THE SITE OF THE WORK AND INFORM HIMSELF/HERSELF FULLY WITH THE WORK INVOLVED, GENERAL AND LOCAL CONDITIONS, ALL FEDERAL, STATE AND LOCAL LAWS, ORDINANCES, RULES AND REGULATIONS AND ALL OTHER PERTINENT ITEMS WHICH MAY AFFECT THE COST AND TIME OF COMPLETION OF THIS PROJECT BEFORE SUBMITTING A BID.
- 9. ALL WORK AND MATERIALS SHALL BE IN ACCORDANCE WITH CODE 8. LONG RADIUS CURVES, EITHER HORIZONTAL OR VERTICAL, MAY BE LAID WITH REQUIREMENTS.
- 10. PRIOR TO SUBMITTING HIS BID, THE CONTRACTOR SHALL CALL THE ATTENTION OF THE ENGINEER TO ANY MATERIAL OR EQUIPMENT HE DEEMS INADEQUATE AND TO ANY ITEM OF WORK OMITTED.
- 11. THE PAY ITEMS SHALL BE AS NOTED IN THE SUMMARY OF QUANTITIES. ANY ITEM OF WORK THAT IS SHOWN ON THE PLANS TO BE PERFORMED BY THE CONTRACTOR, FOR WHICH THERE IS NO PAY ITEM, SHALL BE CONSIDERED INCIDENTAL TO THE COST OF THE PROJECT.
- 12. THE UNDERGROUND CONTRACTOR SHALL BE RESPONSIBLE TO PLACE ON GRADE AND COORDINATE WITH OTHER CONTRACTORS ALL UNDERGROUND STRUCTURE FRAMES SUCH AS CATCH BASINS, INLETS, MANHOLES, HYDRANTS, BUFFALO BOXES, VALVES, ETC. NO ADDITIONAL COMPENSATION SHALL BE PAID AND SAID ADJUSTMENTS SHALL BE CONSIDERED INCIDENTAL TO OTHER ITEMS OF
- 13. THE CONTRACTOR SHALL RESTORE ANY AREA DISTURBED TO A CONDITION EQUAL TO OR BETTER THAN ITS ORIGINAL USE. THIS SHALL INCLUDE FINISH GRADING, ESTABLISHMENT OF A VEGETATIVE COVER (SEEDING OR SOD), GENERAL CLEANUP AND PAVEMENT REPLACEMENT
- 14. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING SAFE AND HEALTHFUL WORKING CONDITIONS THROUGHOUT THE CONSTRUCTION OF THE PROPOSED IMPROVEMENTS.
- 15. THE CONTRACTOR SHALL INFORM THE VILLAGE ENGINEER BEFORE WORK COMMENCES ON EACH CATEGORY OF CONSTRUCTION, I.E. WATER MAIN AND STORM SEWER. A TWENTY-FOUR (24) HOUR NOTICE SHALL BE GIVEN FOR ANY ITEM THAT REQUIRES FINAL TESTING AND INSPECTION SUCH AS WATER MAINS
- S.ALL LOT IRONS DAMAGED OR REMOVED DURING CONSTRUCTION OF THIS PROJECT SHALL BE REPLACED BY THE ENGINEER AND SAID COST OF REPLACEMENT SHALL BE PAID BY THE CONTRACTOR.
- 17.BEFORE ACCEPTANCE BY THE VILLAGE AND FINAL PAYMENT, ALL WORK SHALL BE INSPECTED AND APPROVED BY THE VILLAGE ENGINEER. FINAL PAYMENT SHALL BE THE AFTER ALL OF THE CONTRACTOR'S WORK HAS BEEN APPROVED
- 18. THE CONTRACTOR WILL HAVE IN HIS POSSESSION ON THE JOB SITE A COPY OF THE PLANS AND SPECIFICATIONS DURING CONSTRUCTION.
- 19.IF ANY APPROVED EQUAL ITEMS ARE REQUIRED, THE CONTRACTOR SHALL CONTACT THE VILLAGE FOR APPROVAL.
- 20. ANY DRAIN AND/OR FIELD TILE ENCOUNTERED BY THE CONTRACTOR DURING THE INSTALLATION OF THE IMPROVEMENTS SHALL BE RETURNED TO ORIGINAL CONDITION. THE VILLAGE SHALL BE NOTIFIED OF THE FIELD TILE TO WITNESS THE REPAIR AND DOCUMENT ITS LOCATION. THIS WORK SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. INCIDENTAL TO THE CONTRACT.
- ALL ROAD SIGNS, STREET SIGNS AND TRAFFIC SIGNS WHICH NEED TO BE RELOCATED OR MOVED DUE TO CONSTRUCTION SHALL BE TAKEN DOWN AND STORED BY THE CONTRACTOR AT HIS OWN EXPENSE, EXCEPT THOSE WHICH ARE NECESSARY FOR PROPER TRAFFIC CONTROL WHICH SHALL BE TEMPORARILY RESET UNTIL COMPLETION OF CONSTRUCTION OPERATIONS. AFTER COMPLETION OF THE WORK, THE CONTRACTOR SHALL RESET, AT HIS EXPENSE, ALL SAID
- 22. THE CONTRACTOR SHALL DISPOSE OF ALL EXCESS EXCAVATION, UNSUITABLE AND UNUSABLE MATERIALS OFFSITE AND AT AN APPROVED LOCATION IN A MANNER THAT PUBLIC OR PRIVATE PROPERTY WILL NOT BE DAMAGED OR ENDANGERED. THIS WORK IS CONSIDERED AS INCIDENTAL TO THE COST OF THE
- 23. NO EXCAVATIONS WILL BE PERMITTED TO REMAIN OPEN OVER ANY WEEKEND.
- 24. "BAND-SEAL" OR SIMILAR COUPLINGS SHALL BE USED WHEN JOINING SEWER PIPES OF DISSIMILAR MATERIALS.
- 25. AS-BUILT DRAWINGS SHALL BE PREPARED BY THE VILLAGE CONSULTANT AND SUBMITTED TO THE VILLAGE ENGINEER AS SOON AS THE SITE IMPROVEMENTS ARE COMPLETED. ANY CHANGE IN LENGTH, LOCATION OR ALIGNMENT SHALL BE
- 26. THE CONTRACTOR IS RESPONSIBLE FOR COORDINATING ANY REQUIRED 20. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING SAFE AND HEALTHFUL WORKING CONDITIONS THROUGHOUT THE CONSTRUCTION OF THE
- 27. SPECIAL ATTENTION IS DRAWN TO THE FACT THAT ARTICLE 105.06 OF THE STANDARD SPECIFICATIONS REQUIRES THE CONTRACTOR TO HAVE A 21. BEFORE ACCEPTANCE BY THE VILLAGE ALL WORK SHALL BE INSPECTED AND COMPETENT SUPERINTENDENT ON THE PROJECT SITE AT ALL TIMES, APPROVED BY THE VILLAGE OR ITS REPRESENTATIVES.

 IRRESPECTIVE OF THE AMOUNT OF WORK SUBJECT. THE SUPERINTENDENT SHALL BE CAPABLE OF READING AND UNDERSTANDING THE PLANS AND SPECIFICATIONS, SHALL HAVE FULL AUTHORITY TO EXECUTE ORDERS TO EXPEDITE THE PROJECT, SHALL BE RESPONSIBLE FOR SCHEDULING AND HAVE CONTROL OF ALL WORK AS THE AGENT OF THE CONTRACTOR. FAILURE TO COMPLY WITH THIS PROVISION WILL RESULT IN A SUSPENSION OF WORK AS BROWNED IN APTICLE 108 07 PROVIDED IN ARTICLE 108.07.

VILLAGE OF SCHAUMBURG GENERAL NOTES AND CONSTRUCTION SPECIFICATIONS (CONT.)

- 29. IF GROUNDWATER IS ENCOUNTERED, THE DEWATERING SHALL BE CONSIDERED INCIDENTAL WHEN NECESSARY. PRIOR TO COMMENCING ANY DEWATERING, T CONTRACTOR SHALL SUBMIT FOR APPROVAL A DEWATERING PLAN INDICATING WELL POINT LOCATIONS, PUMP SIZES AND CAPACITIES AND ALL DISCHARGE

VILLAGE OF SCHAUMBURG WATER MAIN CONSTRUCTION

- ALL WATER MAIN CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE "STANDARD SPECIFICATIONS FOR WATER AND SEWER MAIN CONSTRUCTION IN ILLINOIS", LATEST EDITION, THE NOTES ON THE PLANS, AND IN ACCORDANCE WITH CODES AND ORDINANCES OF THE VILLAGE OF SCHAUMBURG, ILLINOIS.
- 2. ALL WATER MAIN SHALL BE DUCTILE IRON PIPE CLASS 52 WITH EITHER MECHANICAL OR PUSH-ON JOINTS AND SHALL CONFORM TO ANSI A21.51-96, AWWA C151 AND ANSI A21.11-00, AWWA C111. PIPE SHALL BE MANUFACTURED IN THE UNITED STATES.
- 3. ALL FITTINGS SHALL BE COMPACT DUCTILE IRON AND SHALL CONFORM TO AWWA/ANSI C153/A21.53_00. FITTINGS SHALL BE U.L. LISTED CLASS 350 TYLER GRIFFIN OR APPROVED EQUAL. FITTINGS SHALL BE MANUFACTURED IN THE UNITED STATES.
- ALL PIPE AND FITTINGS SHALL BE CEMENT LINED IN ACCORDANCE WITH AWWA/ANSI C104/A21.4-95.
- ALL FITTINGS SHALL BE MECHANICAL JOINT AND INSTALLED WITH RETAINER GLANDS UNLESS OTHERWISE SHOWN ON THE DRAWINGS. ALL FASTENERS SHALL BE 304 STAINLESS STEEL-BOLTS AND NUTS.
- 6. ALL MECHANICAL JOINT FITTINGS. VALVES. AND HYDRANTS SHALL BE RESTRAINED WITH RETAINER GLANDS. RETAINER GLANDS SHALL BE EBAA IRON SERIES 1100 MEGALUG, UNI-FLANGE SERIES 1400, STARGRIP SERIES 3000, OR SIGMA ONE LOK SLD.
- ALL WATER MAIN SHALL BE WRAPPED WITH POLYETHYLENE IN ACCORDANCE WITH AWWA/ANSI C105/A21.5-99.
- STANDARD PIPE BY DEFLECTIONS AT THE JOINTS. MAXIMUM DEFLECTIONS AT PIPE JOINTS AND LAYING RADIUS FOR THE VARIOUS PIPE LENGTHS SHALL BE IN ACCORDANCE WITH AWWA C600-99. WHEN RUBBER GASKETED PIPE IS LAID ON A CURVE, THE PIPE SHALL BE JOINTED IN A STRAIGHT ALIGNMENT AND THEN DEFLECTED TO THE CURVED ALIGNMENT. TRENCHES SHALL BE MADE WIDER ON CURVES FOR THIS PURPOSE.
- STANDARD OPERATING NUT, AND OPEN IN A COUNTER-CLOCKWISE DIRECTION. GATE VALVES SHALL BE CLOW, OR MUELLER RESILIENT WEDGE GATE VALVE IN ACCORDANCE WITH AWWA C509-94. GATE VALVES SHALL BE IN VALVE VAULTS. ALL GATE VALVES SHALL BE CONSISTENT THROUGHOUT A DEVELOPMENT. NO BUTTERFLY VALVES ARE ALLOWED.
- 10. ALL VALVE BOXES SHALL BE CAST IRON, TWO (2) PIECE 51/4" SHAFTS. ALL VALVE BOXES SHALL EITHER BE TRENCH ADAPTÉR MODEL 6 BY AMERICAN FLOW CONTROL OR SCREW TYPE TYLER MODEL 666-S AND ATTACHED TO THE HYDRANT BARREL WITH GRIP ARMS AS MANUFACTURED BY BLR OR APPROVED EQUAL. LIDS TO BE MARKED "WATER" (VALVE BOX EXTENSIONS IF REQUIRED ARE CONSIDERED INCIDENTAL).
- ALL HYDRANTS SHALL BE IN ACCORDANCE WITH AWWA C502-94 AND SHALL BE MUELLER MODEL # A-423 OR CLOW MODEL # F-2545 BREAK-FLANGE TYPE HYDRANT (RED) WITH 5.25" VALVE. 4.5" PUMPER AND 2-2.50" HOUSE CONNECTIONS. STAINLESS STEEL LOWER STEM. ALL HYDRANTS SHALL BE ONE MODEL THROUGHOUT A DEVELOPMENT.
- 12. SLEEVES SHALL BE MECHANICAL JOINT DUO-SLEEVES. D.I. DUO-SLEEVES SHALL BE PROVIDED AT LOCATIONS SHOWN ON THE PLANS OR AS REQUIRED.
- 13. ALL TEES, BENDS, FIRE HYDRANTS, PLUGS, AND VALVES SHALL BE ADEQUATELY SUPPORTED WITH A CONCRETE BASE AND SUPPORTED LATERALLY WITH POURED IN PLACE THRUST BLOCKING AGAINST UNDISTURBED EARTH.
- 14. ALL WATER MAINS SHALL HAVE A MINIMUM DEPTH OF COVER OF 5.5'.
- 15. ALL PRESSURE TAPS TO AN EXISTING VILLAGE MAIN SHALL BE MADE WITH A STAINLESS STEEL CASCADE TAPPING SLEEVE AND TAPPING VALUE WHICH CONSTRUCTED IN VALUE VAULT.
- 16. THE CONTRACTOR SHALL OBTAIN, ERECT, MAINTAIN, AND REMOVE ALL SIGNS BARRICADES, FLAGMEN, AND OTHER CONTROL DEVICES AS MAY BE NECESSARY 30. IF THE CONTRACTOR PROPOSES TO USE AN EQUAL PRODUCT FOR ANY OF THE FOR THE PURPOSE OF REGULATING, WARNING, OR GUIDING TRAFFIC. PLACEMENT AND MAINTENANCE OF ALL TRAFFIC CONTROL DEVICES SHALL BE IN ACCORDANCE WITH THE APPLICABLE PARTS OF ARTICLE 107.14 OF THE STANDARD SPECIFICATIONS AND THE ILLINOIS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS. CONTRACTOR SHALL FURNISH A TRAFFIC CONTROL PLAN FOR IDOT OR VILLAGE APPROVAL IF REQUIRED.
- 17. ALL WORK AND MATERIALS SHALL BE IN ACCORDANCE WITH CODE REQUIREMENTS.
- 18. THE CONTRACTOR SHALL RESTORE ANY AREA DISTURBED TO A CONDITION EQUAL TO OR BETTER THAN ITS ORIGINAL USE. THIS SHALL INCLUDE FINISH GRADING, ESTABLISHMENT OF A VEGETATIVE COVER (SEEDING OR SOD) GENERAL CLEANUP, AND PAVEMENT REPLACEMENT.
- WATER SERVICE PIPES, AND THE EXCAVATION AROUND CATCH BASINS. MANHOLES, INLETS, AND OTHER APPURTENANCES WHICH OCCUR WITHIN THE GUTTERS OR WHERE THE EDGE OF THE TRENCH SHALL BE WITHIN 2' OF SAID IMPROVEMENTS SHALL BE BACKFILLED WITH CA-7 LIMESTONE (IDOT CERTIFIED) OR OTHER MATERIAL AS INDICATED ON PLANS OR CONTRACT DOCUMENTS, AND MECHANICALLY COMPACTED IN 6"-12" LIFTS DEPENDING ON COMPACTION EQUIPMENT USED.
- PROPOSED IMPROVEMENTS.

VILLAGE OF SCHAUMBURG WATER MAIN CONSTRUCTION SPECIFICATIONS (CONT.)

- 22. EASEMENTS FOR THE EXISTING UTILITIES, BOTH PUBLIC AND PRIVATE, AND UTILITIES WITHIN PUBLIC RIGHTS-OF-WAY ARE SHOWN ON THE PLANS RESPONSIBLE FOR DETERMINING THE EXACT LOCATION IN THE FIELD OF THESE UTILITY LINES AND THEIR PROTECTION FROM DAMAGE DUE TO CONSTRUCTION SHALL NOTIFY THE ENGINEER SO THAT THE CONFLICT MAY BE RESOLVED.
- PROTECTION AGENCY SUBTITLE F: PUBLIC WATER SUPPLIES. CHAPTER II: ENVIRONMENTAL PROTECTION AGENCY, PARTS 651-654 TECHNICAL POLICY CHLORINE SOLUTIONS. STATEMENTS, SECTION 653.119.
- 24. WHENEVER POSSIBLE, A WATER MAIN MUST BE LAID AT LEAST HORIZONTALLY FROM ANY EXISTING OR PROPOSED DRAIN OR SEWER LINE SEPARATION OF 10'. A WATER MAIN MAY BE LAID CLOSER THAN 10' TO A PREVENTION PROCEDURES: STORM OR SANITARY SEWER PROVIDED THAT THE WATER MAIN INVERT IS AT LEAST 18" ABOVE THE CROWN OF THE SEWER, AND IS EITHER IN A SEPARATI TRENCH OR IN THE SAME TRENCH ON AN UNDISTURBED EARTH SHELI LOCATED TO ONE SIDE OF THE SEWER. IF IT IS IMPOSSIBLE TO OBTAIN PROPER HORIZONTAL OR VERTICAL SEPARATION AS DESCRIBED ABOVE, THEN THE SEWER MUST ALSO BE CONSTRUCTED OF WATER MAIN TYPE MATERIAL DUCTILE IRON PIPE WITH SLIP—ON OR MECHANICAL JOINTS. PRESTRESSEL REINFORCED CONCRETE PIPE WITH ASTM C-443 JOINTS, ETC.) AND PRESSURE TESTED TO THE MAXIMUM EXPECTED SURCHARGE HEAD TO ASSURE WATER TIGHTNESS BEFORE BACKFILLING.
- 25. WHENEVER WATER MAINS MUST CROSS HOUSE SEWERS, STORM SEWERS, OR SANITARY SEWERS, THE WATER MAIN SHALL BE LAID AT SUCH AN ELEVATION THAT THE INVERT OF THE WATER MAIN IS 18" ABOVE THE CROWN OF THE DRAIN OR SEWER. THIS VERTICAL SEPARATION MUST BE MAINTAINED FOR THAT PORTION OF THE WATER MAIN LOCATED WITHIN 10' HORIZONTALLY OF ANY SEWER OR DRAIN CROSSED. THIS MUST BE MEASURED AS THE NORMAL DISTANCE FROM THE WATER MAIN TO THE DRAIN OR SEWER. IF IT IS IMPOSSIBLE TO OBTAIN THE PROPER VERTICAL SEPARATION AS DESCRIBED ABOVE OR IF IT IS NECESSARY FOR THE WATER MAIN TO PASS UNDER A SEWER OR DRAIN, THEN THE SEWER MUST BE CONSTRUCTED OF WATER MAIN ON EACH SIDE OF THE CROSSING UNTIL THE NORMAL DISTANCE FROM THE WATER MAIN TO THE SEWER OR DRAIN LINE IS AT LEAST 10'. IN MAKING SUCH CROSSINGS, CENTER A LENGTH OF WATER MAIN PIPE OVER/UNDER THE MUST CROSS UNDER A SEWER, A VERTICAL SEPARATION OF 18" BETWEEN THE INVERT OF THE SEWER AND THE CROWN OF THE WATER MAIN SHALL BE LINES TO PREVENT THEIR SETTLING AND BREAKING THE WATER MAIN.
- ALL VALVES SHALL BE GATE VALVES AND SHALL HAVE A NON-RISING STEM, A 26. VALVE VAULTS SHALL BE ADJUSTED WITH A MAXIMUM OF 12" OF ADJUSTING 12" WILL NECESSITATE THE ADDITION OF A BARREL SECTION.
 - 27. HYDROSTATIC TESTS THE CONTRACTOR SHALL PERFORM HYDROSTATIC TESTS SPECIFICATIONS FOR WATER AND SEWER MAIN CONSTRUCTION IN ILLINOIS, LATEST EDITION, AND APPLICABLE PROVISIONS OF AWWA C600 AND C603. THE WATER MAINS SHALL BE PRESSURE TESTED AT 150 PSI. THE TEST PRESSURE SHALL NOT DROP MORE THAN 2 PSI FOR THE DURATION OF THE TEST. THE GAUGE SHALL BE OF GOOD QUALITY AND CONDITION, AND BE FLUID FILLED. THE GAUGE SHALL HAVE A LARGE ENOUGH RANGE FOR THE PRESSURE BEING TESTED AND SHALL BE CAPABLE OF READING A MINIMUM PRESSURE INCREMENT OF 1 PSI. ALLOWABLE LEAKAGE SHALL BE AS SET FORTH IN AWWA C600, LATEST EDITION. THE TESTING LENGTH SHALL BE LIMITED TO IF MORE THAN 1,000' OF WATER MAIN IS TESTED, THE ALLOWABLE LEAKAGE WILL BE BASED UPON 1,000'. THE DURATION OF THE TEST SHALL BE FOR 2 HOURS MINIMUM.
 - 28. DISINFECTION OF THE WATER MAINS _ UPON COMPLETION OF THE NEWLY LAID WATER MAINS. THE WATER MAINS SHALL BE DISINFECTED IN ACCORDANCE WITH SAMPLES AND HAVING BACTERIOLOGICAL TESTING PERFORMED AS REQUIRED BY THE IEPA. THE CONTRACTOR SHALL FURNISH TO THE VILLAGE THE REQUIRED DOCUMENTATION, TEST RESULTS, ETC., REQUIRED BY THE IEPA FOR PLACING THE WATER MAINS OR SERVICE LINES IN SERVICE AND/OR SECURING AN 4.11.3.1 OPERATING PERMIT.
 - SCHAUMBURG WATER DEPARTMENT AT 847/923-6612.
 - ITEMS CONTAINED IN THE VILLAGE OF SCHAUMBURG WATER MAIN DOCUMENTATION FROM THE MANUFACTURER THAT THE PROPOSED PRODUCT MEETS THE VILLAGE STANDARDS TO THE VILLAGE OF SCHAUMBURG DIRECTOR THE CONTRACTOR.
 - DETAILS.
 - 32. ALL DEWATERING SHALL BE CONSIDERED INCIDENTAL TO THE PROJECT.
- 19. ALL TRENCHES CAUSED BY THE CONSTRUCTION OF SEWERS, WATER MAINS, 33. NO WATER SERVICE TAPS SHALL BE MADE PRIOR TO THE VILLAGE RECEIVING THE IEPA OPERATIING PERMIT.
 - PRIOR TO SHUTTING DOWN THEIR WATER SERVICE AND DRIVEWAY REMOVAL.
 - SPECIFICATIONS EVERY SERVICE AND MAIN REPAIR SHALL BE DOCUMENTED AND INSPECTED PRIOR TO BACKFILL. INSPECTION SHALL BE DONE AT THE TIME OF REPAIR ON SITE.

AWWA C651-14 SECTION 4.11: DISINFECTION PROCEDURES WHEN CUTTING INTO OR REPAIRING EXISTING MAINS

4.11.1 GENERAL

4.11.2 BASIC DISINFECTION

- EXPOSED. BY MAINTAINING A DEWATERED TRENCH. AND BY KEEPING SERVICE PRIOR TO OBTAINING BACTERIOLOGICAL RESULTS. ALL PIPE MATERIALS BEING USED IN THE REPAIR IN A CLEAN AND SANITARY CONDITION.
- 2.INSPECTING AND CLEANING, FOLLOWED BY DISINFECTION OF SPRAYING OR SWABBING WITH A MINIMUM 1 PERCENT CHLORINE SOLUTION:
- a.EXPOSED PORTIONS OF EXISTING PIPE INTERIOR SURFACES b.PIPE MATERIALS USED IN THE REPAIR c.HANDHELD MATERIALS AND TOOLS USED TO MAKE THE REPAIR
- FLUSH THEIR SERVICE LINES UPON RETURN TO SERVICE.

4.11.3 SELECTION OF DISINFECTION PROCEDURE

SHUTDOWN, REQUIRING DISINFECTION PROCEDURES EQUIVALENT TO THOSE OF IN ACCORDANCE WITH DIVISION IV, SECTION 41 OF THE STANDARD A NEW MAIN INSTALLATION. THE PROCEDURES DESCRIBED IN SEC. 4.11.3.1 WHERE PRACTICAL AND APPROPRIATE CONSIDERING THE RISKS OF PUBLIC THROUGH 4.11.3.3 DESCRIBED THE CONTAMINATION RISKS AND THE EXPOSURE TO HIGH CONCENTRATIONS OF CHLORINE, IN ADDITION TO THE ASSOCIATED DISINFECTION AND SAMPLING REQUIREMENTS FOR DIFFERENT PROCEDURES PREVIOUSLY DESCRIBED IN THIS STANDARD, THE SECTION OF SCENARIOS OF PIPELINE REPAIR. SPECIFIC SITUATIONS NOT CAPTURED PIPE IN WHICH THE BREAK IS LOCATED SHALL BE ISOLATED, ALL SERVICE BELOW NEED TO NE EVALUATED AND THE APPROPRIATE DISINFECTION AND CONNECTIONS SHUT OFF, AND THE SECTION FLUSHED AND DISINFECTED. IF SAMPLING METHODS FOLLOWED.

4.11.3.3 FOR DISTRIBUTION MAINS MAY NEED TO BE MODIFIED FOR LARGE SCOUR FLUSHING AS 3.0 FT/SEC (0.91 M/SEC) OR GREATER FOR A TRANSMISSION MAINS. LARGE MAINS MAY NEED ADDITIONAL WORK (SUCH MINIMUM OF THREE PIPE VOLUMES AND CONTINUE UNTIL DISCOLORED WATER AS HAVING A VALVE REPLACED OR REQUIRING A SPECIAL ORDER ON A IS NOT OBSERVED AND THE CHLORINE RESIDUA IS RESTORED TO THE CONNECTION), MAY BE OUT OF SERVICE FOR MORE THAN A DAY, OR MAY LEVELS MAINTAINED IN THE DISTRIBUTION SYSTEM BY THE WATER UTILITY. THE AMERICAN WATER WORKS ASSOCIATION, PROCEDURE DESIGNATION, AWWA NOT BE ABLE TO ACCOMMODATE A SCOUR FLUSH. THESE MODIFICATIONS C651, LATEST EDITION. THE CONTRACTOR IS RESPONSIBLE FOR COLLECTING NEED TO BE MADE ON A CASE-BY-CASE BASIS BUT SHOULD STILL TAKE FOR LARGER-DIAMETER PIPE (12 IN. AND GREATER), IF A WATER VELOCITY INTO ACCOUNT THE PROCEDURES OUTLINED IN ANSI/AWWA C651.

OF SCHAUMBURG WATER DEPARTMENT PERSONNEL. PLEASE CONTACT THE ACTIVITIES ARE WELL CONTROLLED AND A FULL SHUTDOWN IS NOT NEEDED, RESIDUAL). THUS MAINTAINING POSITIVE PRESSURE TO THE AREA OF SHUTDOWN AND AROUND THE BREAK SITE AT ALL TIMES. THE REPAIR SITE IS EXPOSED AD FOR VERY—LARGE—DIAMETER PIPE (WHERE PERSONNEL MAY SAFELY ENTER THE TRENCH S ADEQUATELY DEWATERED SO THAT THE REPAIR SITE CAN BE THE PIPE), IN LIEU OF FLUSHING FOLLOWING DISINFECTION, THE INTERIOR OF CONSTRUCTION NOTES OR DETAILS, THE CONTRACTOR SHALL PROVIDE CLEANED AND DISINFECTED BY SPRAYING OR SWABBING WITH A MINIMUM 1 THE PIPE AT THE REPAIR SITE MAY BE CLEARED BY SWEEPING OR HIGH PERCENT CHLORINE SOLUTION. THE WATER MAIN IS THEN RETURNED TO PRESSURE WASH USING POTABLE WATER BEFORE DISINFECTION. STANDING OF PUBLIC WORKS. THE VILLAGE OF SCHAUMBURG DIRECTOR OF PUBLIC SERVICE WITH FLUSHING TO OBTAIN THREE VOLUMES OF WATER TURNOVERS, WATER AND DEBRIS FROM THE CLEANING MUST BE REMOVED FROM THE WORKS SHALL APPROVE THE PROPOSED EQUAL PRODUCT PRIOR TO USE BY MAKING SURE THAT THE FLUSHED WATER IS VISUALLY CLEAR. NO PIPE PRIOR TO DISINFECTION. THE AFFECTED PIPE SHALL BE DISINFECTED BACTERIOLOGICAL TESTING IS NECESSARY. IT IS ADVISABLE TO CHECK FOR BY SWABBING OR SPRAYING WITH A MINIMUM 1 PERCENT CHLORINE 31. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL INSTALL INLET FILTER ON A TYPICAL SYSTEM CHLORIDE RESIDUAL, AND IF NOT FOUND, TO CONTINUE SOLUTION. ALL OPEN LID PAVEMENT STRUCTURES AND CURB INLETS TRIBUTARY TO THE FLUSHING UNTIL RESIDUALS ARE RESTORED TO LEVELS MAINTAINED IN THE CONSTRUCTION AREA IN ACCORDANCE WITH SWPPP, SPECIAL PROVISIONS AND DISTRIBUTION SYSTEM BY THE WATER UTILITY-IF THE SYSTEM OPERATES AFTER FOLLOWING THE APPROPRIATE METHODS ABOVE, PRIOR TO RETURNING WITH A DISINFECTANT RESIDUAL.

CONTROLLED PIPE REPAIR WITH DEPRESSURIZATION AFTER SHUTDOWN. IN PROPER NOTIFICATION OF THE AFFECTED CUSTOMERS. LIMITS OF EXISTING OR PROPOSED PAVEMENTS, SIDEWALKS, AND CURB AND 34. ALL RESIDENT AND BUSINESSES SHELL BE NOTIFIED A MINIMUM OF 48 HOURS THIS SITUATION. AFTER THE REPAIR SITE HAS BEEN EXPOSED AND SECURED FROM TRENCH SOIL/WATER CONTAMINATION, THE WATER MAIN IS 4.11.4 TEMPORARY SERVICE LINES 35. WHEN EITHER A BUILDING SEWER OR PUBLIC SEWER IS DISTURBED AND DEPRESSURIZED BY A SHUTDOWN TO COMPLETE THE REPAIR. THE REPAIR SUBSEQUENTLY REPAIRED, ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH LOCAL SITE SHOULD BE CLEANED AND DISINFECTED BY SPRAYING OR SWABBING TEMPORARY WATER SERVICE LINES TO CUSTOMERS DURING MAIN REPAIR WITH A MINIMUM 1 PERCENT CHLORIDE SOLUTIONS. THE WATER MAIN IS ACTIVITIES SHALL BE DISINFECTED PRIOR TO USE. MATERIALS SHALL MEET THEN RETURNED TO SERVICE WITH FLUSHING TO SCOUR THE PIPE AND THE NSF/ANSI 61 CERTIFICATION FOR POTABLE WATER USE. DISINFECTION OBTAIN THREE VOLUMES OF WATER TURNOVER, MAKING SURE THAT THE SHOULD BE ACCOMPLISHED BY THE PROCEDURES IN SEC. 4.4 OR 4.5 FLUSHED WATER IS VISUALLY CLEAR. IT IS ADVISABLE TO CHECK FOR A FOLLOWED BY SCOUR FLUSHING AT 3.0 FT/SEC (0.91 M/SEC) OR GREATER TYPICAL SYSTEM CHLORIDE RESIDUAL, AND IF NTO FOUND, TO CONTINUE FOR A MINIMUM OF THREE PIPE VOLUMES (SEE TABLE 3), OR UNTIL THE FLUSHING UNTIL RESIDUALS ARE RESTORED TO LEVELS MAINTAINED IN THE WATER RUNS VISUALLY CLEAR AND PREFERABLY A MEASURABLE CHLORINE DISTRIBUTION SYSTEM BY THE WATER UTILITY-IF THE SYSTEM OPERATES RESIDUAL IS RESTORED. WITH A DISINFECTANT RESIDUAL.

AWWA C651-14 SECTION 4.11: DISINFECTION PROCEDURES WHEN CUTTING INTO OR REPAIRING EXISTING MAINS (CONTINUED)

WHEN THE EXISTING PIPE HAS TO BE OPENED AND THE INTERIOR SURFACES OF THE WATER SYSTEM EXPOSED TO THE ENVIRONMENT, ADDITIONAL ACCORDING TO AVAILABLE RECORDS. THE CONTRACTOR SHALL BE THE PLANNED, UNPLANNED, OR EMERGENCY REPAIR OF A WATER MAIN OR PROCEDURES NEED TO BE FOLLOWED. THE EXISTING PIPE SHOULD BE APPURTENANCES (E.G., VALVE) IS TIME SENSITIVE—AN IMPORTANT GOAL IS INSPECTED AND CLEANED WITH THE HELP OF FLUSHING WATER INTO THE OPERATIONS. IF EXISTING UTILITY LINES OF ANY NATURE ARE ENCOUNTERED TO MINIMIZE THE DISRUPTION OF WATER SERVICE TO CUSTOMERS. TRENCH, WHERE POSSIBLE, UNTIL THE FLUSH WATER RUNS VISUALLY CLEAR. WHICH CONFLICT IN LOCATION WITH NEW CONSTRUCTION, THE CONTRACTOR NONETHELESS, THE REPAIR WORK NEEDS TO BE ACCOMPLISHED USING THE REPAIR SITE SHOULD BE ACCESSIBLE AND THE TRENCH ADEQUATELY SANITARY AND SAFE PROCEDURES BY WELL-TRAINED CREWS WITH PROPER DEWATERED SO THAT THE REPAIR SITE CAN BE CLEANED AND DISINFECTED 23. WATER MAINS AND WATER SERVICE LINES SHALL BE PROTECTED FROM SUPERVISION AND GUIDANCE. REFER TO PREVENTIVE AND CORRECTIVE BY SPRAYING OR SWABBING WITH A MINIMUM 1 PERCENT CHLORINE SANITARY SEWERS, STORM SEWERS, COMBINED SEWERS, HOUSE SEWER SERVICE MEASURES DESCRIBED PREVIOUSLY IN SEC. 4.8.2, 4.8.4, AND 4.8.5. SOLUTION. ADDITIONALLY, ANY ACCESSIBLE UPSTREAM AND DOWNSTREAM CONNECTIONS, AND DRAINS IN ACCORDANCE WITH TITLE 35: ENVIRONMENTAL FOLLOW ALL PERSONAL PROTECTION PRECAUTIONS WHEN WORKING WITH INTERIOR OF THE EXISTING PIPE SHOULD BE DISINFECTED BY SWABBING OR SPRAYING WITH A MINIMUM OF 1 PERCENT CHLORIDE SOLUTION. IF THE REPAIR REQUIRES A FULL PIPE SECTION REPLACEMENT, THE NEW PIPE SHOULD BE INSPECTED, CLEANED AND DISINFECTED FROM BOTH ENDS BY SWABBING WITH A MINIMUM 1 PERCENT CHLORIDE SOLUTION. THE WATER SHOULD LOCAL CONDITIONS EXIST WHICH WOULD PREVENT A LATERAL WORK SHOULD FOLLOW BASIC DISINFECTION AND CONTAMINATION MAIN MAY THEN BE RETURNED TO SERVICE AFTER FLUSHING TO SCOUR THE PIPE AND OBTAIN THREE VOLUMES OF WATER TURNOVER. THE FLUSHED 1. PREVENTING CONTAMINANTS FROM ENTERING THE EXISTING PIPE WATER SHOULD RUN VISUALLY CLEAR, HAVE A MEASURABLE CHLORIDE DURING THE REPAIR SUCH AS BY MAINTAINING POSITIVE PRESSURE IN RESIDUAL IF THE SYSTEM OPERATES WITH A RESIDUAL, AND BE CHECKED THE LEAKING PIPE UNTIL THE REPAIR SITE ON THE PIPE IS FULLY WITH BACTERIOLOGICAL TESTING. THE PIPELINE MAY BE RETURNED TO

UNCONTROLLED PIPE BREAK WITH A LIKELIHOOD OF WATER CONTAMINATION OR LOSS OF SANITARY CONDITIONS DURING REPAIR. IN SITUATIONS IN WHICH THE EXISTING MAIN TO BE REPAIRED COULD NOT BE PROTECTED AND KEPT FREE OF CONTAMINATION AND THERE ARE OBVIOUS SIGNS OF 3.AS APPROPRIATE, ADVISING AFFECTED CUSTOMERS TO ADEQUATELY CONTAMINATION (E.G., MUDDY TRENCH WATER FLOWING INTO THE BROKEN PIPE AND A LEAKING SEWER PIPE IN THE TRENCH, OR CATASTROPHIC PIPE FAILURE WHERE PIPE IS OPEN AND THERE IS A LIKELIHOOD THAT CONTAMINATION WAS DRAWN INTO THE ACTIVE SYSTEM) OR WHEN A CONTROLLED REPAIR SITUATION TURNS INTO A SITUATION IN WHICH THE TYPE MATERIAL (AS NOTED IN ITEM 24). THIS CONSTRUCTION MUST EXTEND THE DISINFECTION PROCEDURE SELECTED SHOULD BE DETERMINED BY THE INTERNAL PIPE AND WATER HAVE BECOME CONTAMINATED, THE PROCEDURES CONDITIONS AND SEVERITY OF THE MAIN BREAK. MANY LEAKS OR BREAKS OUTLINES IN SEC. 4.3, 4.4, 4.5, OR 4.6 SHOULD BE FOLLOWED WHERE BE REPAIRED UNDER CONTROLLED CONDITIONS WITHOUT PRACTICAL. THE METHODS SPECIFY CHLORINE DOSES OF 25-300 MG/L; SEWER TO BE CROSSED SO THAT THE JOINTS WILL BE EQUIDISTANT FROM THE DEPRESSURIZING THE WATER MAIN, SUCH AS WHEN APPLYING A CLAMP TO HOWEVER, SUCH LEVELS MAY PRESENT GREATER HARM IF THE LINE OR SEWER AND AS REMOTE THEREFROM AS POSSIBLE. WHERE A WATER MAIN A SMALL CRACK OR HOLE, THUS PREVENTING CONTAMINANTS FROM SERVICE CANNOT BE RELIABLY ISOLATED OR SHUT DOWN EXPOSURE OF ENTERING THE WATER SYSTEM. IN MOST OTHER SITUATIONS, THE WATER CUSTOMERS TO HIGH CONCENTRATIONS OF CHLORINE CANNOT BE MAINTAINED, ALONG WITH MEANS TO SUPPORT THE LARGER SIZED SEWER MAIN CAN BE MAINTAINED PRESSURIZED UNTIL THE BREAK SITE IS SECURED CONTROLLED. FREE CHLORINE RESIDUALS UP TO 4 MG/L (BASED ON AND THE PIPE IS FULLY EXPOSED. SOME CIRCUMSTANCES (E.G., SEVER ANNUAL AVERAGES) ARE ALLOWED BY FEDERAL DRINKING WATER EROSION OF THE LOCAL ENVIRONMENT OR ICING OF THE ROADWAY) THAT REGULATIONS; THEREFORE THIS LEVEL IS SUGGESTED AS A MINIMUM TO BE RINGS. NO MORE THAN THREE ADJUSTING RINGS ARE ALLOWED. THERE IS A IMPACT PUBLIC SAFETY MAY REQUIRE THAT WATER PRESSURE BE MAINTAINED FOR AT LEAST 16 HR IN CONJUNCTION WITH FLUSHING, 2" MINIMUM RING SIZE AND ALL RINGS 4" AND LESS SHALL BE HDPE (H526 SUBSTANTIALLY REDUCED PRIOR TO EXPOSING THE PIPE IN THE AREA OF COLIFORM SAMPLING, AND ASSOCIATED CUSTOMER EDUCATION. SUCH OF AASHTO AND ASTMD1248.84). ANY REQUIRED ADJUSTMENT GREATER THAN THE LEAK. IN SOME CASES, SITUATIONS BECOME CATASTROPHIC WHERE SITUATIONS REQUIRE CAREFUL REVIEW AND NEED TO BALANCE THE PUBLIC THERE IS A PIPE BLOWOUT AND A LOSS OF WATER PRESSURE PRIOR TO HEALTH RISKS OF THE PIPELINE FAILURE AS WELL AS THE REPAIR PROCESS.

> THE SLUG CHLORINATION METHOD IS EMPLOYED, THE DOSE MAY BE INCREASED TO AS MUCH AS 300 MG/L AND THE CONTACT TIME REDUCED NOTE THAT THE PROCEDURES EXPLAINED IN SEC. 4.11.3.1, 4.11.3.2, AND TO AS LITTLE AS 15 MIN. AFTER CHLORINATION AND REPAIR, PERFORM

OF 3.0 FT/SEC (0.91 M/SEC) CANNOT BE ACHIEVED, IT IS A DESIRABLE TO FLUSH AT THE MAXIMUM FLOW FOR THE MAIN UNTIL THREE PIPE VOLUMES HAVE BEEN DISPLACED BEFORE RETURNING THE MAIN TO SERVICE. THE FLUSHED WATER SHOULD RUN VISUALLY CLEAR, AND HAVE TYPICAL SYSTEM MATCHES THE TYPE OF OTHER VALUES ON THE PROJECT AND SHALL BE 29. WATER VALVES AND FIRE HYDRANTS SHALL ONLY BE OPERATED BY VILLAGE CONTROLLED PIPE REPAIR WITHOUT DEPRESSURIZATION. IN THIS SITUATION, CHLORINE RESIDUAL (IF THE SYSTEM OPERATES WITH A DISINFECTANT

THE PIPE TO SERVICE, THE EFFICACY OF THE DISINFECTION PROCEDURE SHALL BE VERIFIED BY TESTING FOR THE ABSENCE OF COLIFORM BACTERIA. IF ALLOWED BY LOCAL REGULATIONS, THE PIPELINE MAY BE RETURNED TO LIMITED SERVICE PRIOR TO OBTAINING BACTERIOLOGICAL RESULTS WITH


SP $\mathbf{\omega}$ S ш


FILENAME:


13379S2 2 DATE: 10/18/24 JOB NO.


13379


SHEET












RIGID AND FLEXIBLE PIPE INSTALLATION DETAIL


SANITARY SEWERS





7/1/15

STD. DWG. NO. 3











OHRMAN S, ILLINOIS

H

N:\Projects 13000-13999\13379\ENG\13379D5.dgn Default User=bmcgovern

RESERVED

PARKING

S

	REFERENCED SPECIFICATIONS ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE APPLICABLE SECTIONS OF THE FOLLOWING,	PIPE MATERIAL PIPE SPECIFICATIONS JOINT SPECIFICATIONS ASTM C 700 ASTM C 425	E. EROSION AND SEDIMENT CONTROL
	EXCEPT AS MODIFIED HEREIN OR ON THE PLANS: * STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION (LATEST EDITION), BY THE ILLINOIS DEPARTMENT OF TRANSPORTATION (IDOT SS) FOR ALL IMPROVEMENTS EXCEPT SANITARY SEWER AND WATER MAIN CONSTRUCTION;	VITRIFIED CLAY PIPE ASTM C-700 ASTM C-425 REINFORCED CONCRETE SEWER PIPE ASTM C-76 ASTM C-443	THE CONTRACTOR SHALL INSTALL THE EROSION AND SEDIMENT CONTROL DEVICES AS SHOWN ON THE APPROVED EROSION AND SEDIMENT CONTROL PLAN.
	* SEWER AND SPECIFICATIONS CONSTRUCTION; * STANDARD SPECIFICATIONS, SEWER AND SEWER MAIN CONSTRUCTION IN ILLINOIS, LATEST	CAST IRON SOIL PIPE ASTM A-74 ASTM C-564	EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE FUNCTIONAL PRIOR TO HYDROLOGIC DISTURBANCE OF THE SITE.
	* STANDARD SPECIFICATIONS FOR WATER AND SEWER MAIN CONSTRUCTION IN ILLINOIS, LATEST EDITION (SSWS) FOR SANITARY SEWER AND WATER MAIN CONSTRUCTION; * VILLAGE OF <u>SCHAUMBURG</u> MUNICIPAL CODE; * THE METROPOLITAN WATER RECLAMATION DISTRICT OF GREATER CHICAGO (MWRD) WATERSHED	DUCTILE IRON PIPE ANSI A21.51 ANSI A21.11	3. ALL DESIGN CRITERIA, SPECIFICATIONS, AND INSTALLATION OF EROSION AND SEDIMENT CONTROL
	MANAGEMENT ORDINANCE AND TECHNICAL GUIDANCE MANUAL; * IN CASE OF CONFLICT BETWEEN THE APPLICABLE ORDINANCES NOTED, THE MORE STRINGENT SHALL TAKE PRECEDENCE AND SHALL CONTROL ALL CONSTRUCTION.	POLYVINYL CHLORIDE (PVC) PIPE 6-INCH TO 15-INCH DIAMETER SDR 26 ASTM D-3034 ASTM D-3212 18-INCH TO 27-INCH DIAMETER F/DY=46 ASTM F-679 ASTM D-3212	PRACTICES SHALL BE IN ACCORDANCE WITH THE ILLINOIS URBAN MANUAL. 4. A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN SHALL BE MAINTAINED ON THE
В	NOTIFICATIONS	HIGH DENSITY POLYETHYLENE (HDPE) ASTM D-3350 ASTM D-3261,F-2620 (HEAT FUSION) ASTM D-3035 ASTM D-3212,F-477 (GASKETED)	SITE AT ALL TIMES. 5. INSPECTIONS AND DOCUMENTATION SHALL BE PERFORMED, AT A MINIMUM:
_	THE MWRD LOCAL SEWER SYSTEMS SECTION FIELD OFFICE MUST BE NOTIFIED AT LEAST TWO (2) WORKING DAYS PRIOR TO THE COMMENCEMENT OF ANY WORK (CALL 708-588-4055 OR SEND EMAIL NOTIFICATION WITH	WATER MAIN QUALITY PVC 4-INCH TO 36-INCH ASTM D-2241 ASTM D-3139	a) UPON COMPLETION OF INITIAL EROSION AND SEDIMENT CONTROL MEASURES, PRIOR TO ANY SOIL DISTURBANCE.
2	PROJECT NAME, LOCATION AND PERMIT NUMBER TO <u>WMOJOBSTART@MWRD.ORG</u>). THE VILLAGE OF SCHAUMBURG ENGINEERING DEPARTMENT AND PUBLIC MUST BE NOTIFIED AT LEAST 24 HOURS	4-INCH TO 12-INCH AWWA C900 ASTM D-3139 14-INCH TO 48-INCH AWWA C905 ASTM D-3139	b) ONCE EVERY SEVEN (7) CALENDAR DAYS AND WITHIN 24 HOURS OF THE END OF A STORM EVENT WITH GREATER THAN 0.5 INCH OF RAINFALL OR LIQUID EQUIVALENT PRECIPITATION.
3	PRIOR TO THE START OF CONSTRUCTION AND PRIOR TO EACH PHASE OF WORK. CONTRACTOR SHALL DETERMINE ITEMS REQUIRING INSPECTION PRIOR TO START OF CONSTRUCTION OR EACH WORK PHASE. THE CONTRACTOR SHALL NOTIFY ALL UTILITY COMPANIES PRIOR TO BEGINNING CONSTRUCTION FOR THE	THE FOLLOWING MATERIALS ARE ALLOWED ON A QUALIFIED BASIS SUBJECT TO DISTRICT REVIEW AND APPROVAL PRIOR TO PERMIT ISSUANCE. A SPECIAL CONDITION WILL BE ADDED TO THE PERMIT WHEN THE PIPE MATERIAL BELOW IS USED FOR SEWER CONSTRUCTION OR A CONNECTION IS MADE.	6. SOIL DISTURBANCE SHALL BE CONDUCTED IN SUCH A MANNER AS TO MINIMIZE EROSION. IF STRIPPING, CLEARING, GRADING, OR LANDSCAPING ARE TO BE DONE IN PHASES, THE CO-PERMITTEE SHALL PLAN FOR APPROPRIATE SOIL EROSION AND SEDIMENT CONTROL MEASURES.
	EXACT LOCATIONS OF UTILITIES AND FOR THEIR PROTECTION DURING CONSTRUCTION. IF EXISTING UTILITIES ARE ENCOUNTERED THAT CONFLICT IN LOCATION WITH NEW CONSTRUCTION, IMMEDIATELY NOTIFY THE ENGINEER SO THAT THE CONFLICT CAN BE RESOLVED. CALL J.U.L.I.E. AT 1-800-892-0123.	PIPE MATERIAL PIPE SPECIFICATIONS JOINT SPECIFICATIONS	7. A STABILIZED MAT OF CRUSHED STONE MEETING THE STANDARDS OF THE ILLINOIS URBAN MANUAL SHALL BE INSTALLED AT ANY POINT WHERE TRAFFIC WILL BE ENTERING OR LEAVING A CONSTRUCTION SITE. SEDIMENT OR SOIL REACHING AN IMPROVED PUBLIC RIGHT-OF-WAY, STREET, ALLEY OR PARKING
<u>C</u>	GENERAL NOTES	POLYPROPYLENE (PP) PIPE	AREA SHALL BE REMOVED BY SCRAPING OR STREET CLEANING AS ACCUMULATIONS WARRANT AND TRANSPORTED TO A CONTROLLED SEDIMENT DISPOSAL AREA.
1	ALL ELEVATIONS SHOWN ON PLANS REFERENCE THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88). CONVERSION FACTOR IS0.0 FT.	12-INCH TO 24-INCH DOUBLE WALL ASTM F-2736 D-3212, F-477 30-INCH TO 60-INCH TRIPLE WALL ASTM F-2764 D3212, F-477	8. CONCRETE WASHOUT FACILITIES SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE ILLINOIS URBAN MANUAL AND SHALL BE INSTALLED PRIOR TO ANY ON SITE CONSTRUCTION ACTIVITIES INVOLVING
	MWRD, THE MUNICIPALITY AND THE OWNER OR OWNER'S REPRESENTATIVE SHALL HAVE THE AUTHORITY TO INSPECT, APPROVE, AND REJECT THE CONSTRUCTION IMPROVEMENTS.	······································	CONCRETE. 9. MORTAR WASHOUT FACILITIES SHALL BE CONSTRUCTED IN ADDITION TO CONCRETE WASHOUT
3	THE CONTRACTOR(S) SHALL INDEMNIFY THE OWNER, ENGINEER, MUNICIPALITY, MWRD, AND THEIR AGENTS,	O ALL CANITARY CENTER CONCERNICATION (AND CENTER CONCERNICATION OF	FACILITIES FOR ANY BRICK AND MORTAR BUILDING ENVELOPE CONSTRUCTION ACTIVITIES.
4	ETC., FROM ALL LIABILITY INVOLVED WITH THE CONSTRUCTION, INSTALLATION, OR TESTING OF THIS WORK ON THE PROJECT. THE PROPOSED IMPROVEMENTS MUST BE CONSTRUCTED IN ACCORDANCE WITH THE ENGINEERING PLANS	8. ALL SANITARY SEWER CONSTRUCTION (AND STORM SEWER CONSTRUCTION IN COMBINED SEWER AREAS), REQUIRES STONE BEDDING WITH STONE ¼ "TO 1" IN SIZE, WITH MINIMUM BEDDING THICKNESS EQUAL TO ¼ THE OUTSIDE DIAMETER OF THE SEWER PIPE, BUT NOT LESS THAN FOUR (4) INCHES NOR MORE THAN EIGHT (8) INCHES. MATERIAL SHALL BE CA-7, CA-11 OR CA-13 AND SHALL BE EXTENDED AT LEAST 12"	10. TEMPORARY DIVERSIONS SHALL BE CONSTRUCTED AS NECESSARY TO DIRECT ALL RUNOFF FROM HYDROLOGICALLY DISTURBED AREAS TO AN APPROPRIATE SEDIMENT TRAP OR BASIN. VOLUME CONTROL FACILITIES SHALL NOT BE USED AS TEMPORARY SEDIMENT BASINS.
	AS APPROVED BY MWRD AND THE MUNICIPALITY UNLESS CHANGES ARE APPROVED BY MWRD, THE MUNICIPALITY, OR AUTHORIZED AGENT. THE CONSTRUCTION DETAILS, AS PRESENTED ON THE PLANS, MUST BE FOLLOWED. PROPER CONSTRUCTION TECHNIQUES MUST BE FOLLOWED ON THE IMPROVEMENTS INDICATED ON THE PLANS.	ABOVE THE TOP OF THE PIPE WHEN USING PVC. 9. NON-SHEAR FLEXIBLE-TYPE COUPLINGS SHALL BE USED IN THE CONNECTION OF SEWER PIPES OF DISSIMILAR PIPE MATERIALS.	11. DISTURBED AREAS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED SHALL BE STABILIZED WITH TEMPORARY OR PERMANENT MEASURES WITHIN SEVEN (7) DAYS.
5	THE LOCATION OF VARIOUS UNDERGROUND UTILITIES WHICH ARE SHOWN ON THE PLANS ARE FOR INFORMATION ONLY AND REPRESENT THE BEST KNOWLEDGE OF THE ENGINEER. VERIFY LOCATIONS AND	10. ALL MANHOLES SHALL BE PROVIDED WITH BOLTED, WATERTIGHT COVERS. SANITARY LIDS SHALL BE CONSTRUCTED WITH A CONCEALED PICKHOLE AND WATERTIGHT GASKET WITH THE WORD "SANITARY"	12. ALL FLOOD PROTECTION AREAS AND VOLUME CONTROL FACILITIES SHALL, AT A MINIMUM, BE PROTECTED WITH A DOUBLE-ROW OF SILT FENCE (OR EQUIVALENT).
6	ELEVATIONS PRIOR TO BEGINNING THE CONSTRUCTION OPERATIONS. ANY EXISTING PAVEMENT, SIDEWALK, DRIVEWAY, ETC., DAMAGED DURING CONSTRUCTION OPERATIONS	CAST INTO THE LID. 11. WHEN CONNECTING TO AN EXISTING SEWER MAIN BY MEANS OTHER THAN AN EXISTING WYE, TEE, OR	13. VOLUME CONTROL FACILITIES SHALL NOT BE CONSTRUCTED UNTIL ALL OF THE CONTRIBUTING DRAINAGE AREA HAS BEEN STABILIZED.
	AND NOT CALLED FOR TO BE REMOVED SHALL BE REPLACED AT THE EXPENSE OF THE CONTRACTOR.	AN EXISTING MANHOLE, ONE OF THE FOLLOWING METHODS SHALL BE USED: a) A CIRCULAR SAW-CUT OF SEWER MAIN BY PROPER TOOLS ("SHEWER-TAP" MACHINE OR SIMILAR)	14. SOIL STOCKPILES SHALL, AT A MINIMUM, BE PROTECTED WITH PERIMETER SEDIMENT CONTROLS. SOIL STOCKPILES SHALL NOT BE PLACED IN FLOOD PROTECTION AREAS OR THEIR BUFFERS.
	MATERIAL AND COMPACTION TESTING SHALL BE PERFORMED IN ACCORDANCE WITH THE REQUIREMENTS OF THE MUNICIPALITY, MWRD, AND OWNER.	AND PROPER INSTALLATION OF HUBWYE SADDLE OR HUB-TEE SADDLE. b) REMOVE AN ENTIRE SECTION OF PIPE (BREAKING ONLY THE TOP OF ONE BELL) AND REPLACE WITH A WYE OR TEE BRANCH SECTION.	15. EARTHEN EMBANKMENT SIDE SLOPES SHALL BE STABILIZED WITH APPROPRIATE EROSION CONTROL BLANKET.
8	THE UNDERGROUND CONTRACTOR SHALL MAKE ALL NECESSARY ARRANGEMENTS TO NOTIFY ALL INSPECTION AGENCIES.	c) WITH PIPE CUTTER, NEATLY AND ACCURATELY CUT OUT DESIRED LENGTH OF PIPE FOR INSERTION OF PROPER FITTING, USING "BAND SEAL" OR SIMILAR COUPLINGS TO HOLD IT FIRMLY IN PLACE.	16. STORM SEWERS THAT ARE OR WILL BE FUNCTIONING DURING CONSTRUCTION SHALL BE PROTECTED BY APPROPRIATE SEDIMENT CONTROL MEASURES.
	ALL NEW AND EXISTING UTILITY STRUCTURES ON SITE AND IN AREAS DISTURBED DURING CONSTRUCTION SHALL BE ADJUSTED TO FINISH GRADE PRIOR TO FINAL INSPECTION. RECORD DRAWINGS SHALL BE KEPT BY THE CONTRACTOR AND SUBMITTED TO THE ENGINEER AS SOON AS	12. WHENEVER A SANITARY/COMBINED SEWER CROSSES UNDER A WATERMAIN, THE MINIMUM VERTICAL DISTANCE FROM THE TOP OF THE SEWER TO THE BOTTOM OF THE WATERMAIN SHALL BE 18 INCHES. FURTHERMORE, A MINIMUM HORIZONTAL DISTANCE OF 10 FEET BETWEEN SANITARY/COMBINED SEWERS AND WATERMAINS SHALL BE MAINTAINED UNLESS: THE SEWER IS LAID IN A SEPARATE	17. THE CONTRACTOR SHALL EITHER REMOVE OR REPLACE ANY EXISTING DRAIN TILES AND INCORPORATE THEM INTO THE DRAINAGE PLAN FOR THE DEVELOPMENT. DRAIN TILES CANNOT BE TRIBUTARY TO A SANITARY OR COMBINED SEWER. DRAIN TILES ALLOWED IN COMBINED SEWER AREA FOR GREEN INFRASTRUCTURE PRACTICES.
	UNDERGROUND IMPROVEMENTS ARE COMPLETED. FINAL PAYMENTS TO THE CONTRACTOR SHALL BE HELD UNTIL THEY ARE RECEIVED. ANY CHANGES IN LENGTH, LOCATION OR ALIGNMENT SHALL BE SHOWN IN RED. ALL WYES OR BENDS SHALL BE LOCATED FROM THE DOWNSTREAM MANHOLE. ALL VALVES, B-BOXES, TEES OR BENDS SHALL BE TIED TO A FIRE HYDRANT. SANITARY SEWER	TRENCH, KEEPING A MINIMUM 18" VERTICAL SEPARATION; OR THE SEWER IS LAID IN THE SAME TRENCH WITH THE WATERMAIN LOCATED AT THE OPPOSITE SIDE ON A BENCH OF UNDISTURBED EARTH, KEEPING A MINIMUM 18" VERTICAL SEPARATION. IF EITHER THE VERTICAL OR HORIZONTAL DISTANCES DESCRIBED CANNOT BE MAINTAINED, OR THE SEWER CROSSES ABOVE THE WATER MAIN, THE SEWER SHALL BE CONSTRUCTED TO WATER MAIN STANDARDS OR IT SHALL BE ENCASED WITH A WATER MAIN QUALITY CARRIER PIPE WITH THE ENDS SEALED.	18. IF DEWATERING SERVICES ARE USED, ADJOINING PROPERTIES AND DISCHARGE LOCATIONS SHALL BE PROTECTED FROM EROSION AND SEDIMENTATION. DEWATERING SYSTEMS SHOULD BE INSPECTED DAILY DURING OPERATIONAL PERIODS. THE SITE INSPECTOR MUST BE PRESENT AT THE COMMENCEMENT OF DEWATERING ACTIVITIES.
1	THE CONTRACTOR SHALL TAKE MEASURES TO PREVENT ANY POLLUTED WATER, SUCH AS GROUND AND SURFACE WATER, FROM ENTERING THE EXISTING SANITARY SEWERS.	13. ALL EXISTING SEPTIC SYSTEMS SHALL BE ABANDONED. ABANDONED TANKS SHALL BE FILLED WITH GRANULAR MATERIAL OR REMOVED.	19. THE CONTRCTOR SHALL BE RESPONSIBLE FOR TRENCH DEWATERING AND EXCAVATION FOR THE INSTALLATION OF SANITARY SEWERS, STORM SEWERS, WATERMAINS AS WELL AS THEIR SERVICES
2	A WATER-TIGHT PLUG SHALL BE INSTALLED IN THE DOWNSTREAM SEWER PIPE AT THE POINT OF SEWER CONNECTION PRIOR TO COMMENCING ANY SEWER CONSTRUCTION. THE PLUG SHALL REMAIN IN PLACE UNTIL REMOVAL IS AUTHORIZED BY THE MUNICIPALITY AND/OR MWRD AFTER THE SEWERS HAVE BEEN	14. ALL SANITARY MANHOLES, (AND STORM MANHOLES IN COMBINED SEWER AREAS), SHALL HAVE A MINIMUM INSIDE DIAMETER OF 48 INCHES, AND SHALL BE CAST IN PLACE OR PRE-CAST REINFORCED CONCRETE.	AND OTHER APPURTENANCES. ANY TRENCH DEWATERING, WHICH CONTAINS SEDIMENT SHALL PASS THROUGH A SEDIMENT SETTLING POND OR EQUALLY EFFECTIVE SEDIMENT CONTROL DEVICE. ALTERNATIVES MAY INCLUDE DEWATERING INTO A SUMP PIT, FILTER BAG OR EXISTING VEGETATED UPSLOPE AREA. SEDIMENT LADEN WATERS SHALL NOT BE DISCHARGE TO WATERWAYS, FLOOD PROTECTION AREAS OR THE COMBINED SEWER SYSTEM.
	TESTED AND ACCEPTED. DISCHARGING ANY UNPOLLUTED WATER INTO THE SANITARY SEWER SYSTEM FOR THE PURPOSE OF SEWER FLUSHING OF LINES FOR THE DEFLECTION TEST SHALL BE PROHIBITED WITHOUT PRIOR APPROVAL	15. ALL SANITARY MANHOLES, (AND STORM MANHOLES IN COMBINED SEWER AREAS), SHALL HAVE PRECAST "RUBBER BOOTS" THAT CONFORM TO ASTM C-923 FOR ALL PIPE CONNECTIONS. PRECAST SECTIONS SHALL CONSIST OF MODIFIED GROOVE TONGUE AND RUBBER GASKET TYPE JOINTS.	20. ALL PERMANENT EROSION CONTROL PRACTICES SHALL BE INITIATED WITHIN SEVEN (7) DAYS FOLLOWING THE COMPLETION OF SOIL DISTURBING ACTIVITIES.
4	FROM THE MUNICIPALITY OR MWRD. ALL SANITARY SEWER CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS FOR WATER AND SEWER MAIN CONSTRUCTION IN ILLINOIS (LATEST EDITION).	16. ALL ABANDONED SANITARY SEWERS SHALL BE PLUGGED AT BOTH ENDS WITH AT LEAST 2 FEET LONG NON-SHRINK CONCRETE OR MORTAR PLUG.	21. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE MAINTAINED AND REPAIRED AS NEEDED ON A YEAR-ROUND BASIS DURING CONSTRUCTION AND ANY PERIODS OF CONSTRUCTION SHUTDOWN UNTIL PERMANENT STABILIZATION IS ACHIEVED.
5	ALL FLOOR DRAINS SHALL DISCHARGE TO THE SANITARY SEWER SYSTEM.	17. EXCEPT FOR FOUNDATION/FOOTING DRAINS PROVIDED TO PROTECT BUILDINGS, OR PERFORATED PIPES ASSOCIATED WITH VOLUME CONTROL FACILITIES, DRAIN TILES/FIELD TILES/UNDERDRAINS/PERFORATED	22. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED WITHIN THIRTY (30) DAYS AFTER PERMANENT SITE STABILIZATION.
	ALL DOWNSPOUTS AND FOOTING DRAINS SHALL DISCHARGE TO THE STORM SEWER SYSTEM. ALL SANITARY SEWER PIPE MATERIALS AND JOINTS (AND STORM SEWER PIPE MATERIALS AND JOINTS IN A COMBINED SEWER AREA) SHALL CONFORM TO THE FOLLOWING:	PIPES ARE NOT ALLOWED TO BE CONNECTED TO OR TRIBUTARY TO COMBINED SEWERS, SANITARY SEWERS, OR STORM SEWERS TRIBUTARY TO COMBINED SEWERS IN COMBINED SEWER AREAS. CONSTRUCTION OF NEW FACILITIES OF THIS TYPE IS PROHIBITED; AND ALL EXISTING DRAIN TILES AND PERFORATED PIPES ENCOUNTERED WITHIN THE PROJECT AREA SHALL BE PLUGGED OR REMOVED, AND SHALL NOT BE CONNECTED TO COMBINED SEWERS, SANITARY SEWERS, OR STORM SEWERS TRIBUTARY TO COMBINED SEWERS.	23. THE EROSION AND SEDIMENT CONTROL MEASURES SHOWN ON THE PLANS ARE THE MINIMUM REQUIREMENTS. ADDITIONAL MEASURES MAY BE REQUIRED, AS DIRECTED BY THE ENGINEER, SITE INSPECTOR, OR MWRD.
		18. A BACKFLOW PREVENTER IS REQUIRED FOR ALL DETENTION BASINS TRIBUTARY TO COMBINED SEWERS. REQUIRED BACKFLOW PREVENTERS SHALL BE INSPECTED AND EXERCISED ANNUALLY BY THE PROPERTY OWNER TO ENSURE PROPER OPERATION, AND ANY NECESSARY MAINTENANCES SHALL BE PERFORMED TO	

MWRD GENERAL NOTES

SCHAUMBURG, ILLINOIS
SCHAUMBURG, ILLINOIS FILENAME: 13379MWRD-GN DATE: 10/18/24

JOB NO. 13379

SHEET

MWRD-GN


19 OF 21

10/13/2022

STD. DWG. NO.18

PAGE NO. 19

N:\Projects 13000-13999\13379\ENG\13379MWRD-GN.dgn Default User=bmcgovern



<u>LEGEND</u>


•••• DISTURBED DEVELOPMENT AREA (3.14 AC.)

NEW IMPERVIOUS AREA (2.44 AC)

PERVIOUS AREA (0.70 AC)

EXISTING BUILDING AREA (0.33 AC)

MAINTENANCE/IN-KIND REPLACEMENT AREA



MWRD STORMWATER SUMMARY

EXISTING AREA SUMMARY: PROPOSED AREA SUMMARY: **RELEASE RATE SUMMARY:** ACTUAL RELEASE RATE PER PERMIT 84-422 IMPERVIOUS = 2.90 AC IMPERVIOUS = 2.44 AC = 1.62 CFS PERVIOUS = 0.31 AC PERVIOUS = 0.77 AC

TOTAL AREA = 3.21 AC TOTAL AREA = 3.21 AC RUNOFF C-FACTOR = 0.86RUNOFF C-FACTOR = 0.79

RELEASE RATE = 0.995 (0.31 CFS/AC)RELEASE RATE = 0.642 (0.20 CFS/AC)DET. VOL. REQ'D = 0.611 AC-FT (MRM TP-40) DET. VOL. REQ'D = 1.045 AC-FT (MRM BUL 75

0.94 AC-FT (MWRD PERMIT #84-422) DETENTION VOLUME REQ'D =

REDEV. DETENTION VOL. REQ'D = 0.44 AC-FT (INCREMENTAL) VOLUME CONTROL CREDIT = -0.20 AC-FT TOTAL DETENTION VOLUME REQ'D = 1.18 AC-FT ADDITIONAL 10% PER VILLAGE = 0.12 AC-FT TOTAL STORAGE REQ'D = 1.50 AC-FT TOTAL STORAGE PROV'D = 1.58 AC-FT

BMP VOLUME SUMMARY: VOLUME CONTROL PROVIDED = 0.20 AC-FT VOLUME CONTROL REQUIRED = 0.20 AC-FT

PRO RATED EXISTING RELEASE RATE = 0.31 CFS/ACRE

ALLOWABLE RELEASE RATE PER RATE MAP = 0.20 CFS/ACRE

RELEASE RATE FOR PROPOSED DEVELOPMENT AREA = 0.642 CFS (3.21 ACRES X 0.2 CFS/ACRE)

RELEASE RATE FOR REMAINING 2.08 ACRE SERVICE AREA = 0.623 CFS (2.01 ACRES X 0.31 CFS/ACRE)

ALLOWABLE RELEASE RATE FOR PROPOSED RESTRICTOR = 1.27 CFS (0.642 CFS + 0.623 CFS)

MAINTENANCE PLAN FOR ROHRMAN KIA

THE OWNER OF BOB ROHRMAN KIA, WITH FACILITIES AS SHOWN ON THIS EXHIBIT, SHALL ASSUME RESPONSIBILITY FOR THE FOLLOWING PERPETUAL MAINTENANCE ACTIVITIES:

1. DETENTION SYSTEM

AS NEEDED:
- REMOVAL OF SEDIMENT AND DEBRIS FROM SUBSURFACE VAULT SEDIMENTATION CHAMBER WHEN THE SEDIMENT ZONE IS FULL AS WELL AS FROM INLET AND OUTLET PIPES. SEDIMENTS SHOULD BE TESTED FOR TOXICANTS IN COMPLIANCE WITH APPLICABLE DISPOSAL REQUIREMENTS IF LAND USES IN THE CATCHMENT INCLUDE COMMERCIAL OR INDSUTRIAL ZONES, OR IF INDICATIONS OF POLLUTION ARE NOTICED.

QUARTERLY:
- FLOATING DEBRIS SHOULD BE REMOVED.

ONCE PER YEAR:
- INSPECTION OF SUBSURFACE VAULT AND CONTROL STRUCTURES.

2. OUTLET CONTROL STRUCTURE
- INSPECT RESTRICTOR AND REMOVE DEBRIS IF CLOGGED OR DISCHARGED REDUCED.

3. VEGETATED AREAS

- NEED FOR PLANTING, RESEEDING, OR SODDING. SUPPLEMENT ALTERNATIVE NATIVE VEGETATION IF A SIGNIFICANT PORTION HAS NOT ESTABLISHED (50% OF THE SURFACE AREA AFTER SECOND GROWING SEASON). RESEED WITH ALTERNATIVE NATIVE GRASS SPECIES IF ORIGINAL GRASS COVER HAS NOT SUCCESSFULLY ESTABLISHED.

- CHECK FOR INVASIVE VEGETATION, REMOVE WHEN POSSIBLE.


- REGULAR MOWING TO CONTROL VEGETATION; IT IS RECOMMENDED THAT NATIVE VEGETATION REMAIN UNCUT.


- DEAD OR DAMAGED NON-NATIVE GRASSY AREAS - REPAIR WITH SEEDING WITH FERTILIZATION OR SEEDING WITH MULCH.

- ALL VEGETATION MUST BE MAINTAINED PER THE APPROVED PLANTING PLAN. PLANTING PLAN.

4. STORM SEWERS
- VISUALLY INSPECT PIPES BY REMOVING MANHOLE LIDS, MAKE REPAIRS AS NECESSARY.
- CHECK FOR SILTATION DEPOSITS AT INLETS AND CATCH BASINS AS

5. SANITARY SEWER (QUALIFIED SEWER)
- THE SANITARY SEWERS MUST BE MAINTAINED
BY THE OWNER PER MWRD'S OPERATION AND MAINTENANCE
MANUAL FOR SEPARATE SANITARY SEWER SYSTEMS'. SEWERS
SHALL BE CLEANED ON A PERFORMANCE BASIS ANNUALLY.





F

FILENAME: 13379MWRD DATE:

10/18/24 JOB NO. 13379

SHEET 20 OF 21